



COMHAIRLE CONTAE AN CHLÁIR
CLARE COUNTY COUNCIL

Specimin Pricing Document
for
Roads A, B, C, D, E, F
in the
ABC Municipal District

Procuring Authority: Clare County Council

Tenderer:



ITEM	DESCRIPTION	UNIT	NOTIONAL QTY	RATE	AMOUNT
	CC-RMP-00100 - PRELIMINARIES				
	TRAFFIC SAFETY AND MANAGEMENT				
0100/01	Traffic Safety and Management in accordance with Appendix 1/17 Design, construct, maintain and remove all Traffic Management required for shuttle system/ Stop-Go/ All-Stop/diversion or otherwise agreed.	Item	1	€	-
0100/03	Provision of variable message signs for the duration of the works and maintenance of same to display appropriate warning messages, to be located 500m before the start of the works on both ends.	Item	1	€	-
	ROAD SWEEPING AND CLEANING				
0100/05	Road sweeping and cleaning	Item	1	€	-
	FACILITIES FOR LOCAL AUTHORITY, PUBLIC OR PRIVATE UTILITY UNDERTAKERS AND OTHER CONTRACTORS				
0100/07	Facilities for Service Undertakers and other Contractors Provide for affording all reasonable facility to Clare County Council and other contractors or Service Undertakers engaged in authorised work on or adjacent to site	Item	1	€	-
	PROJECT SUPERVISOR FOR THE CONSTRUCTION STAGE				
0100/09	Acceptance of Appointment as Project Supervisor for the Construction Stage	Item	1	€	-
	SAFETY FILE				
0100/11	Safety File, in accordance with Appendix 1/71 and relevant Health and Safety legislation	Item	1	€	-
	AS BUILT RECORDS				
0100/13	As-Built Records in accordance with Appendix 1/70	Item	1	€	-
	CONSTRUCTION MANAGEMENT				
0100/15	Construction Management Plan, Environmental Operating Plan, Waste Management Plan and Quality plan in accordance with Appendix 1/73	Item	1	€	-

[illegible]

	CC-RMP-00500 - DRAINAGE AND SERVICE DUCTS				
	RENEWAL, RAISING OR LOWERING COVERS AND GRATINGS ON EXISTING CHAMBERS AND GULLIES				
0500/01	Gratings; renewed, raised or lowered to match proposed/amended levels	No	10	€	-
0500/02	Covers; 100mm sq.; renewed, raised or lowered to match proposed/amended levels	No	10	€	-
0500/03	Covers; 200mm sq.; renewed, raised or lowered to match proposed/amended levels	No	10	€	-
0500/04	Covers; 600mm sq.; renewed, raised or lowered to match proposed/amended levels	No	10	€	-
0500/05	Covers; 750mm sq.; renewed, raised or lowered to match proposed/amended levels	No	10	€	-
0500/06	Covers; 1000mm sq.; renewed, raised or lowered to match proposed/amended levels	No	10	€	-
0500/07	Covers; 600mm dia.; renewed, raised or lowered to match proposed/amended levels	No	10	€	-
0500/08	Covers; 300mm x 200mm; renewed, raised or lowered to match proposed/amended levels	No	10	€	-
0500/09	Covers; 450mm x 300mm; renewed, raised or lowered to match proposed/amended levels	No	10	€	-
0500/10	Covers; 1200mm x 800mm; renewed, raised or lowered to match proposed/amended levels	No	10	€	-
0500/11	Covers; 1200mm x 600mm; renewed, raised or lowered to match proposed/amended levels	No	10	€	-
0500/12	Covers; 1800mm x 600mm; renewed, raised or lowered to match proposed/amended levels	No	10	€	-
0500/13	Covers; 1800mm x 900mm; renewed, raised or lowered to match proposed/amended levels	No	10	€	-
	CC-RMP-00600 - EARTHWORKS				
	SOFT SPOTS AND OTHER VOIDS				
0600/01	Excavation of soft spots and other voids; below bound pavement layers	m3	100	€	-
0600/02	Filling of soft spots and other voids; below bound pavement layers Class 1/Class 2 fill material	m3	100	€	-

	CC-RMP-00700 - PAVEMENT				
	SURFACE COURSE				
0700/01	HRA 35/14 F surf 40/60 des 45mm thick in carriageway, hardshoulder and hardstrip (PSV 60)	m2	3,000	€	-
0700/02	HRA 35/14 F surf 40/60 des 45mm thick in carriageway, hardshoulder and hardstrip (PSV 65+)	m2	3,000	€	-
0700/03	SMA 10 surf PMB 65/105-60 des 40mm thick in carriageway, hardshoulder and hardstrip PSV 65+	m2	3,000	€	-
0700/04	SMA 10 surf PMB 65/105-60 W des 40mm thick in carriageway, hardshoulder and hardstrip PSV 65+	m2	3,000	€	-
0700/05	SMA 14 surf PMB 65/105-60 des 40mm thick in carriageway, hardshoulder and hardstrip PSV 60	m2	3,000	€	-
0700/06	SMA 14 surf PMB 65/105-60 W des 40mm thick in carriageway, hardshoulder and hardstrip PSV 60	m2	3,000	€	-
0700/07	SMA 14 surf PMB 65/105-60 des 40mm thick in carriageway, hardshoulder and hardstrip PSV 65+	m2	3,000	€	-
0700/08	SMA 14 surf PMB 65/105-60 W des 40mm thick in carriageway, hardshoulder and hardstrip PSV 65+	m2	3,000	€	-
	BINDER COURSE				
0700/09	AC 20 dense bin 40/60 des 60mm thick in carriageway hardshoulder and hardstrip	m2	3,000	€	-
0700/10	AC 20 dense bin 40/60 W des 60mm thick in carriageway hardshoulder and hardstrip	m2	3,000	€	-
0700/11	AC 20 dense bin 70/100 des 60mm thick in carriageway hardshoulder and hardstrip	m2	3,000	€	-
0700/12	AC 20 dense bin 70/100 W des 60mm thick in carriageway hardshoulder and hardstrip	m2	3,000	€	-
	BASE COURSE				
0700/13	AC 32 dense base 40/60 des 100mm thick in carriageway hardshoulder and hardstrip	m2	3,000	€	-
0700/14	AC 32 dense base 40/60 W des 100mm thick in carriageway hardshoulder and hardstrip	m2	3,000	€	-
0700/15	AC 32 dense base 70/100 des 100mm thick in carriageway hardshoulder and hardstrip	m2	3,000	€	-
0700/16	AC 32 dense base 70/100 W des 100mm thick in carriageway hardshoulder and hardstrip	m2	3,000	€	-
	REGULATING COURSE				
0700/17	AC 20 dense bin 70/100 des Regulation Course, thickness varies, in carriageway hardshoulder and hardstrip	t	200	€	-
0700/18	AC 20 dense bin 70/100 W des Regulation Course, thickness varies, in carriageway hardshoulder and hardstrip	t	200	€	-
0700/19	SMA 10 bin 40/60 des regulating course	t	200	€	-
0700/20	SMA 10 bin 40/60 W des regulating course	t	200	€	-
0700/21	SMA 6 bin 40/60 des regulating course	t	200	€	-
0700/22	SMA 6 bin 40/60 W des regulating course	t	200	€	-

CC-RMP-00700 - PAVEMENT (continued)					
BOND COAT					
0700/23	Minimum rate of spread 0.30kg/m2 to comply with B.S. 594987 and in accordance with Appendix 7/4	m2	3,000	€	-
COLD MILLING					
0700/24	Cold milling to a depth of 40mm (including disposal to authorised facility)	m2	3,000	€	-
0700/25	Cold milling to a depth of 100mm (including disposal to authorised facility)	m2	3,000	€	-
0700/26	Cold milling to a depth greater than 100mm but not greater than 200mm (including disposal to authorised facility)	m2	3,000	€	-
0700/27	Extra over; removal of existing geogrid/geotextile	m2	3,000	€	-
SUB-BASE					
0700/28	Unbound Granular Material A, UGM A, in carriageway, hardsholder and hardstrip	m3	100	€	-
GEOTEXTILES/GEOGRIDS					
0700/29	Steel Mesh - made from Class A zinc galvanised steel, using double twist mesh and reinforced with high tensile steel bars or twisted flat wire. The elastic modulus shall be a minimum of 200kN/mm2. The characteristic tensile strength of the grid shall be 50kN/m in both the transverse and longitudinal directions.	m2	3,000	€	-
0700/30	Glass or Polymer Fibre - knitted and coated or impregnated with a bitumen compound. The tensile strength declared under CE marking shall be a minimum of 50kN/m in both directions. They can include a self adhesive coating.	m2	3,000	€	-
0700/31	Geocomposite - Geogrids with an integral non-woven textile backing with the Bitumen Retention Value (Ra) declared under CE marking as a minimum value of 0,35kg/m2.	m2	3,000	€	-

CC-RMP-01200 - TRAFFIC SIGNS AND ROAD MARKINGS					
ROAD MARKINGS					
1200/01	Continuous line; 100mm wide; white; TSM RRM001; centre line; reflectorised	m	100	€	-
1200/02	Continuous line; 150mm wide; white; TSM RRM001; centre line; reflectorised	m	100	€	-
1200/03	Intermittent line; 100mm wide; 3m line; 9m gap; white; TSM RRM002A; centre line; reflectorised	m	100	€	-
1200/04	Intermittent line; 150mm wide; 3m line; 9m gap; white; TSM RRM002A; centre line; reflectorised	m	100	€	-
1200/05	Intermittent line; 100mm wide; 3m line; 3m gap; white; TSM RRM002B; centre line; reflectorised	m	100	€	-
1200/06	Intermittent line; 150mm wide; 3m line; 3m gap; white; TSM RRM002B; centre line; reflectorised	m	100	€	-
1200/07	Intermittent line; 100mm wide; 2m line; 2m gap; yellow; TSM RRM025; edge of carriageway line	m	100	€	-
1200/08	Intermittent line; 150mm wide; 2m line; 2m gap; yellow; TSM RRM025; edge of carriageway line	m	100	€	-
1200/09	Letters and numerals; 2.8m high; white; TSM M114; "STOP"	No	10	€	-
1200/10	Continuous line; 200mm wide; white; TSM RRM017; stop line	No	10	€	-
1200/11	Letters and numerals; 2.8m high; white; TSM M115; triangular yield marking	No	10	€	-
1200/12	Intermittent line; 200mm wide; white; TSM RRM018; yield line	No	10	€	-
1200/13	Letters and numerals; 1.6m high; white; TSM M106; "SLOW"	No	10	€	-
1200/14	Letters and numerals; 2.8m high; white; TSM M106; "SLOW"	No	10	€	-
1200/15	Arrows; 3.6m high; white; RRM005 or RRM006; reflectorised	No	10	€	-
1200/16	Arrows; 5.0m high; white; RRM005 or RRM006; reflectorised	No	10	€	-
1200/17	Arrows; 3.6m high; white; M124 or M125; reflectorised	No	10	€	-
1200/18	Arrows; 5.0m high; white; M124 or M125; reflectorised	No	10	€	-
1200/19	Arrows; 3.6m high; white; M126; reflectorised	No	10	€	-
1200/20	Arrows; 5.0m high; white; M126; reflectorised	No	10	€	-
1200/21	Speed Marking; 4.3m high; white; M108; reflectorised	No	10	€	-
1200/22	Speed Marking; 7.5m high; white; M108; reflectorised	No	10	€	-
RETROREFLECTING ROAD STUDS					
1200/23	Bidirectional; with white reflectors	No	100	€	-
1200/24	Bidirectional; with yellow reflectors	No	100	€	-
1200/25	Bidirectional; with yellow / green reflectors	No	100	€	-
CONTRACT SUM					
				€	-

NOTES TO THE PRICING DOCUMENT - VOLUME C

1 All tendered rates are to be exclusive of Value Added Tax.

The detail provided in this Pricing Submission may be read read in conjunction with TII Requirements for Measurement and Pricing . The rates and prices entered in this Pricing Submission shall be deemed to be the full inclusive value of the work covered by the several items including the following, unless expressly stated otherwise:

- i. Labour and costs in connection therewith
- ii. The supply of materials, goods, storage and costs in connection therewith including delivery to Site. Taking delivery of materials and goods supplied by others, unloading, storage, and costs in connection therewith
- iii. Plant and costs in connection therewith
- iv. Fixing, erecting and installing or placing of materials and goods in position
- v. Temporary Works
- 2 vi. The effect on the phasing of the Works or any element of the Works to the extent set forth or reasonably implied in the documents on which the tender is based
- vii. General obligations, liabilities and risks involved in the execution of the works set forth or reasonably implied in the documents on which the tender is based
- viii. Establishment charges, overheads and profit
- ix. Waste
- x. Attendance and transport for sampling and testing carried out by the Employer's Representative, tests carried out by the Contractor, supplying results of tests carried out by the Contractor and providing test certificates
- xi. Complying with Quality Assurance schemes and providing certificates of conformity
- xii. Preparation and supply of detailed working drawings
- xiii. Awaiting approvals and or consents

5 W indicates mixes produced with a warm mix