


DEMOLITION PLAN
SCALE 1:50
FLOOR AREA = 124m²



- REMOVE ALL EXTERNAL DOORS AND WINDOWS
- REMOVE ALL INTERNAL DOORS, FRAMES, ARCHITRAVE, SKIRTINGS, ECT
- REMOVE ALL INTERNAL WALLS AS NOTED - ALLOW FOR ALL TEMPORARY PROPPING ECT.
- DISCONNECT ALL ELECTRICAL & PLUMBING SERVICES
- GRUB UP EXISTING R.C FOUNDATIONS & BACKFILL FOR NEW FOUNDATIONS
- REMOVE EXISTING ROOF & WALL CLADDING ALONG WITH ALL ASSOCIATED STRUCTURAL STEEL SUPPORTS, COLUMNS & TIMBERS
- REMOVE EXISTING RC FLOOR SLABS & TIMBER FLOOR ECT...
- REMOVE EXISTING GROUND BEAM

GENERAL NOTES

ALL DIMENSIONS AND LEVELS TO BE CONFIRMED ON SITE.
 ALL LEVELS RELATE TO TBM 100.00m (EX. FFL)
 ALL CONCRETE IS TO BE GRADE C30/37 U.N.O.
 ALL LEAN MIX CONCRETE BLINDING IS TO BE GRADE C12/15.
 CONCRETE TO BE PLACED IN ACCORDANCE WITH THE SPECIFICATIONS AND BS8110.
 THE CONTRACTOR SHALL PROVIDE ALL NECESSARY TEMPORARY WORKS AND SHORING DURING THE COURSE OF THE WORKS.
 THE DESIGN, INSTALLATION AND MAINTENANCE OF TEMPORARY WORKS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, UNLESS DETAILED IN THE DRAFT DRAWINGS.
 STRENGTH OF ALL BLOCKWORK TO BE 7.5N U.N.O.
 ALL LINTELS SHALL HAVE MINIMUM 225mm BEARING EACH SIDE OF OPE.
 ALL STEEL BEAMS SHALL HAVE MINIMUM OF 450mm BEARING EACH SIDE OF OPE.
 ALL DPM'S, DPC'S, INSULATION AND DETAILS.

Rev.	Date	Issued For	Amendment	By
0	08/04/26	ISSUED FOR TENDER		AT

TENDER

Project:
GORMANSTON CAMP
HANGER LEAN TO
NEW OFFICE BLOCK

Drawing Title:
DEMOLITION PLAN

CLIENT:
CAPTIAN CIARAN CAREY DEFENCE FORCES

MALACHI CULLEN
CONSULTING ENGINEERS LTD

8 CENTRE COURT, BLYRY BUSINESS & COMMERCIAL PARK, ATHLONE, CO. WESTMEATH N37 A710
T: 090 6420364 E: info@mcullen.ie W: www.mcullen.ie

Scale: 1:50 @ A0 Project no: 26-009 Sheet no: T-02 Rev: 0
 Date: APRIL 26 Drm: A TROY Chk: JD