Cork County Council
Comhairle Contae Chorcaí

Coastal Management Unit



Glengarriff Pontoon Replacement
LAMIS 2026

Volume C - Pricing Document

May-26

Glengarriff Pontoon Replacement LAMIS 2026

Item	Description	Unit	Quantity	Rate €	Amount €	Sub-Total
1	Acceptance of appointment as Project Supervisor for the Construction Stage in accordance with current Health & Safety Regulations.	Item	1		€ -	
2	EL & PL Insurances	sum	1		€ -	
3	Welfare Facilities in compliance with Safety & Welfare at Work Act	sum	1		€ -	
4	Provision of a Waste Management Plan/Licence - to include general waste, pontoons, gangway, H-Piles and all other waste	sum	1		€ -	
5	General Site mobilisation and demobilisation.	Item	1		€ -	
6	Erection of site boundary fencing surrounding Works Areas. The fencing shall prevent the entry of unauthorised persons to the site.	Item	1		€ -	
7	Taking all necessary measures to protect the environment.	Item	1		€ -	
8	Traffic Safety and Management for the duration of the works	Item	1		€ -	
9	Liaison with CCC staff and other relevant statutory agencies	Item	1		€ -	
10	Allowance for working in Tidal waters	Item	1		€ -	€ -
	PONTOONS					
11	Supply, manufacturing of Heavy-Duty Pontoon units with mooring points, 1000mm freeboard, with connections and Timber effect GRC deck. 3m wide Heavy-Duty Pontoon	m	21		€ -	
12	Supply, manufacturing of Heavy-Duty Pontoon units with mooring points, 1000mm freeboard, with connections and Timber effect GRC deck. 2.4 m wide Heavy-Duty Pontoon to include angled section as per Drawing WC-26-023-02	m	21		€ -	
13	Additional buoyancy for ramp landing pontoon	No	1		€ -	
14	200x200DD Rubber Fender for Heavy Duty Pontoon (Mooring & end faces)	m	32		€ -	
15	Timber Fender for Heavy Duty Pontoon (Non mooring face)	m	21		€ -	€ -
	PONTOON ACCESSORIES					
16	Supply of H-Iron braces for connecting pontoon units side to side	No	8		€ -	
17	Supply of sets of float straps	No	24		€ -	
18	Drop-Down Fender Frame & 200x200DD Rubber Fender (Mooring & end faces)	m	32		€ -	€ -
	MOORING SYSTEMS					
19	UC Mooring Points 12m 254x254x89kg UC H-Piles	No	3		€ -	
20	Adjustable UC H-Pile Guides	No	3		€ -	€ -
	ACCESS GANGWAYS & ACCESSORIES					
21	1Nr. 20m long x 1.5m wide galvanised access ramp (width measured between handrails, 2m overall width), complete with handrail, decked with non-slip GRP flooring, 4kN/m² live loading, Hinged at the fixed end. Roller at the pontoon end.	No	1		€ -	
22	Supply and install of tubular handrail	m	18		€ -	
23	Lifebuoy with protective housing	No	1		€ -	
24	Safety ladders	No	2		€ -	
25	Standard anodised aluminium cleats including galvanised steel bolts	No	4		€ -	
26	5T Steel Mooring Bollards galvanised and powder coated	No	4		€ -	€ -
	DELIVERY & INSTALLATION & SITE CLEARANCE					
27	Delivery to site	sum	1		€ -	
28	Installation of new pontoons and gangway	sum	1		€ -	
29	Adapt concrete shore block for hinged ramp connection	sum	1		€ -	
30	Disconnection, Removal and disposal of the existing pontoons, gangway and accessories	sum	1		€ -	€ -
	Sub-total (excluding VAT)				€ -	€ -
		VAT @ 13.5%			€ -	
	Total lump sum price (including VAT)				€ -	
				TOTAL	€ -	