

Cork County Council
Comhairle Contae Chorcaí

Coastal Management Unit



Schull Pontoon Replacement
LAMIS 2026

VOLUME C – PRICING DOCUMENT

June 2026

Schull Pontoon Replacement LAMIS 2026

Item	Description	Unit	Quantity	Rate €	Amount €	Sub-Total
1	Acceptance of appointment as Project Supervisor for the Construction Stage in accordance with current Health & Safety Regulations.	Item	1		€ -	
2	EL & PL Insurances	sum	1		€ -	
3	Welfare Facilities in compliance with Safety & Welfare at Work Act	sum	1		€ -	
4	General Site mobilisation and demobilisation.	Item	1		€ -	
5	Erection of site boundary fencing surrounding Works Areas. The fencing shall prevent the entry of unauthorised persons to the site.	Item	1		€ -	
6	Mobilisation of plant & Equipment - including Delivery - offloading new pontoons - reloading old pontoons	Item	1		€ -	
7	Taking all necessary measures to protect the environment.	Item	1		€ -	
8	Traffic Safety and Management for the duration of the works	Item	1		€ -	
9	Liaison with CCC staff and other relevant statutory agencies	Item	1		€ -	
10	Allowance for working in Tidal waters & provision of safety boat for installation	Item	1		€ -	€ -
PONTOONS & MOORING SYSTEMS						
11	Supply of walkway units with mooring points, 500mm freeboard and hardwood timber fendering (150x45mm) with connections and plain pink GRC deck - standard 3m wide walkway	m	21		€ -	
12	Supply of float straps (2no. straps per float)	No.	10		€ -	
13	Supply of Heavy-Duty Grounding Brackets per float	No.	2			
14	Supply UC H-Piles guides	No.	5		€ -	
15	Supply UC H-Piles 5m x 254mm x 254mm c/w fixing plates and bracketry	No.	5		€ -	
16	Supply of Standard anodised aluminium cleats including galvanised steel bolts	No.	10		€ -	
17	Supply of safety ladder	No.	1		€ -	
18	Supply of Lifebuoy (incl. cabinet, cover & stand)	No.	1		€ -	
19	Supply of galvanised signage pole	No.	1		€ -	
20	Line Marking - Box Hatch with Keep Clear Text	No.	1		€ -	
21	Installation including the following; <ul style="list-style-type: none"> • Removal of existing pontoons and accessories • Disposal of old pontoons • Removal/disposal of existing H piles • Install of 5no. new H piles • Install of 2no. pontoons (1 No. 9m x 3m - 1 No.12m x 3m) • Install of 5no. UC Pile brackets • Install of 1no. Ladder & cleats • Install of 1no. Lifebuoy • Install of 1no. Signage Pole • Complete Line marking 	sum	1		€ -	€ -
22	Removal and dispose of existing pontoon and guide rails in accordance with the Waste Management Act	Sum	1		€ -	
					€ -	€ -
				VAT @ 13.5%	€ -	
Total lump sum price (including VAT)					€ -	