Cork County Council
Comhairle Contae Chorcaí

Coastal Management Unit



Courtmacsherry Pontoon
LAMIS 2026

Pontoon Replacement

Volume C Priced Document

June 2026

Courtmacsherry Pontoon Replacement Units - LAMIS 2026

Item	Description	Unit	Quantity	Rate €	Amount €	Sub-Total
1	Acceptance of appointment as Project Supervisor for the Construction Stage in accordance with current Health & Safety Regulations.	Item	1		€ -	
2	EL & PL Insurances	sum	1		€ -	
3	Welfare Facilities in compliance with Safety & Welfare at Work Act	sum	1		€ -	
4	General Site mobilisation and demobilisation.	Item	1		€ -	
5	Erection of site boundary fencing surrounding Works Areas. The fencing shall prevent the entry of unauthorised persons to the site.	Item	1		€ -	
6	Taking all necessary measures to protect the environment.	Item	1		€ -	
7	Traffic Safety and Management for the duration of the works	Item	1		€ -	
8	Liaison with CCC staff and other relevant statutory agencies	Item	1		€ -	
9	Mobilistaion of plant & Equipment - including Delivery - offloading new pontoons - reloading old pontoons	item	1		€ -	
10	Allowance for working in Tidal waters & provision of safety boat for installation	Item	1		€ -	€ -
	PONTOONS					
11	Supply of walkway units with mooring points, 500mm freeboard and hardwood timber fendering (150x45mm) with connections and grey GRP deck. Standard 2m wide walkway.	m	36		€ -	
	MARINA ACCESSORIES					
12	Supply of Adjustable CHS Pile Guide (External or Internal)	No.	2		€ -	
13	Supply of Standard anodised aluminium cleats including galvanised steel bolts	No.	12		€ -	
14	Supply of 4m cross bracing beams	No	4		€ -	
15	Supply of float straps 50 x 5mm	No.	24		€ -	
16	Supply of safety ladders	No.	1		€ -	
17	Supply of Hard plastic (165x120x50mm)	No	1		€ -	
18	Supply of Bi – Metal Tex Screws 5.5 x 62 GRP	sum	1		€ -	
19	Supply of Dome Washers for Grating	sum	1		€ -	
	DELIVERY & INSTALLATION					
20	Delivery including the following; • Offloading of new pontoons • Reloading old pontoons	sum	1		€ -	
21	• Hire of crane • Removal of existing pontoons • Disposal of old pontoons • Install of 4no. 9m x 2.0m pontoons • Install of pile brackets • Install safety ladder	sum	1		€ -	
22	Removal and dispose of existing pontoons in accordance with the Waste Management Act	sum	1		€ -	€ -
	Sub-total (excluding VAT)					€ -
		VAT @ 13.5%				€ -
	Total lump sum price (including VAT)					€ -