



- THE DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS AND CONTRACT DOCUMENTS.
2. THE ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR CO-ORDINATION OF THE ELECTRICAL SERVICES FOR THE BUILDING IN CONJUNCTION WITH THE MAIN CONTRACTOR'S AND MECHANICAL CONTRACTOR'S INSTALLATION.
3. THE ELECTRICAL CONTRACTOR SHALL ENSURE THAT THE INSTALLATION COMPLIES WITH LOCAL AUTHORITY CODES AND ALL OTHER RELEVANT STANDARDS.
4. THE ELECTRICAL CONTRACTOR WILL BE REQUIRED TO ENSURE SERVICES ARE KEPT LIVE AND OPERATIONAL WITHIN THE CLIENT OCCUPIED AREAS AT ALL TIMES; TO THIS END THE CONTRACTOR SHALL BE RESPONSIBLE FOR SUFFICIENTLY SIZED SECONDARY POWER SOURCES/GENERATORS TO ALL BOARDS FOR CHANGEOVERS AS THEY OCCUR. THESE WORKS SHALL ONLY TAKE PLACE ONCE A PROJECT SPECIFIC METHOD STATEMENT AND A PERMIT TO WORK HAS BEEN SUBMITTED AND APPROVED BY THE ENGINEER AND THE ER.
5. THE CONTRACTORS SHOULD VISIT THE SITE DURING THE TENDER PERIOD TO FAMILIARISE THEMSELVES WITH THE SERVICES AND THEREBY ALLOW IN THEIR TENDERS FOR ALL TEMPORARY WORKS NECESSARY TO KEEP THE BUILDING OPERATIONAL DURING THE CONSTRUCTION.
6. THE CONTRACTOR SHALL INCLUDE FOR STRIPPING OUT ALL REDUNDANT ELECTRICAL SERVICES AS PART OF THE WORKS.
7. THE CONTRACTOR SHALL NOTE THAT ALL WORKS ASSOCIATED WITH THE MODIFICATIONS AND STRIPOUT OF THE EXISTING ELECTRICAL SERVICES SHALL ONLY TAKE PLACE ONCE A PROJECT SPECIFIC METHOD STATEMENT AND A PERMIT TO WORK HAS BEEN SUBMITTED AND APPROVED BY THE ENGINEER AND THE ER.
8. ALL EXISTING SERVICES TO BE DISCONNECTED & REINSTATED AS APPROPRIATE DURING CONSTRUCTION.
9. TO FACILITATE THE REFURBISHMENT OF THE LV SWITCHROOM THE ELECTRICAL CONTRACTOR SHALL INCLUDE FOR BUT SHALL NOT BE LIMITED TO THE FOLLOWING WORKS;

SURVEY EXISTING FIRE DETECTION AND
ALARM INSTALLATION.

DETECTION AND ALARM DEVICES TO BE REMOVED. RECONFIGURE EXISTING DETECTION AND SOUNDER LOOPS TO FACILITATE THE REMOVAL OF ALL DEVICES WITHIN THE LV SWITCH ROOM.

ALL DEVICES REMOVED FROM THE FIRE
DETECTION AND ALARM SYSTEM SHALL BE
PROGRAMMED OFF THE EXISTING FIRE
DETECTION AND ALARM SYSTEM.

DISTRIBUTION

SURVEY EXISTING DISTRIBUTION SERVICES.

ISOLATE AND DISCONNECT POWER SUPPLY
TO SITE TEMPS DB.

ALL FINAL CIRCUITS, WIRING ACCESSORIES
AND LIGHTS TO BE REMOVED.

ISOLATE AND REMOVE REMAINING ELECTRICAL AND ELECTRO-MECHANICAL SERVICES WITHIN THE LV SWITCHROOM.

02	P08	May '26	Issued for Tender	K.M.
01	P08	Mar '26	Issued for Tender	K.M.
Rev	Status	Date	Description	D.E.

Revision 02	Project Drawing Reference 25672-ZZ-Z-ZZZ-DR-VCE-EE-0003		
Status P08	Varming Project Number 25672		
Date December 2025	Checked By J.G.	Drawn By K.M.	Scale As Noted

Client
HSE

Project Title	T2 Upgrade Sligo University Hospital
---------------	---

Drawing Title
Electrical Services
Phase 1
Strip Out Works



Dublin	01 4872300	   
Cork	021 2375080	
Roscommon	090 6602380	
Website	www.varming.ie	
<i>Engineering for the Future</i>		  
QUALITY ISO 9001:2015 NSAI Certified		HEALTH & SAFETY ISO 45001:2018 NSAI Certified
ENVIRONMENT ISO 14001:2015 NSAI Certified		

Titleblock Revision: 2020_2

PHASE 1