



Comhairle Contae Mhaigh Eo
Mayo County Council



Tourism, Recreation and Amenity.

Clare Island Trail Improvement Works

Clare Island, County Mayo

Volume C – Pricing Document

June 2026

Ref	Description	Qty	Unit	Rate	Amount
	PRICING DOCUMENT CLEW BAY CYCLE TRACK SERIES 100 PRELIMINARIES <u>Note. A compound area for storage and accommodation for the Contractor and Engineer has NOT been identified. Allow for all costs and charges associated with arranging a suitable compound. Please allow for all costs and charges for delievery of materials and plant to site.</u>				
1	Erection, servicing and dismantling of stores and messes for the contractor		Item		€ _____
	Public Information				
2	Corriboard Information boards erected on site	4.0	Nr	€ _____	€ _____
	Traffic / Pedestrian Safety & Management				
3	Traffic / pedestrian safety and management, including all necessary guardrails and signage		item		€ _____
4	All roads to be kept free from dirt & debris and vehicles to be washed down on each trip		Item		€ _____
	Health and Safety Requirements				
5	Comply with all obligations pursuant to the Safety, Health and Welfare at work (Construction) Regulations 2013 in respect of the successful tenderer being appointed by the Employer as Project Supervisor for Construction Stage		Item		€ _____
6	Acceptance of the position of Project supervisor for the construction stage (PSCS)		Item		€ _____
7	Preparation of Safety File Information		Item		€ _____
Page Total					

Ref	Description	Qty	Unit	Rate	Amount
	SERIES 100 PRELIMINARIES SUMMARY Page : 1				€ _____
Series 100 Total					

Ref	Description	Qty	Unit	Rate	Amount
	<u>SERIES 200 SITE CLEARANCE</u>				
	Site Clearance				
1	General Site Clearance including the removal with a grader of any vegetation from existing pavement edges to be reused for banking at different locations	0.60	ha	€ _____	€ _____
Page Total					

Ref	Description	Qty	Unit	Rate	Amount
	<u>SERIES 200 SITE CLEARANCE SUMMARY</u>				
	Page : 3				€ _____
Series 200 Total					

Ref	Description	Qty	Unit	Rate	Amount
	<u>SERIES 500 DRAINAGE AND SERVICE DUCTS</u>				
1	Construct Surface Water Drain in trench with depth to invert not exceeding 1.0m as per CC-SCD-00521 Type Z containing uPVC pipe diameter 225mm	50	m	€ _____	€ _____
2	Precast Concrete Gully as per CC-SCD-00510 with grating as per CC-SCD-00512 and frame.	5.0	nr	€ _____	€ _____
3	Open drain Inlets	100.0	nr	€ _____	€ _____
Page Total					

Ref	Description	Qty	Unit	Rate	Amount
	<u>SERIES 500 DRAINAGE AND SERVICE DUCTS SUMMARY</u> Page : 5				€ _____
Page Total					

Ref	Description	Qty	Unit	Rate	Amount
	<u>SERIES 700 PAVEMENTS</u>				
1	Provide joints between existing bituminuous pavements on the L- 5896-1 and on the side roads, with the new pavement construction.	9.0	m	€ _____	€ _____
	Regulation Course				
2	Granular Material Type B to Clause 804 of the CC-SPW-00800 laid in carriageway 70mm.	800.00	t	€ _____	€ _____
	Pavement				
3	Granular Material Type B to Clause 804 of the CC-SPW-00800 laid in carriageway 100mm.	1250.00	t	€ _____	€ _____
	Surface Treatment SERIES 900				
4	Double Surface Dressing as per Design summary 7 of the I.A.T guidelines for surface dressing in Ireland. Cationic 70% Bitumen Emulsion shall be used on unbound material.	5000	m ²	€ _____	€ _____
Series 500 Total					

Ref	Description	Qty	Unit	Rate	Amount
	<u>SERIES 700 & 900 PAVEMENTS SUMMARY</u>				
	Page : 8				€ _____
Page Total					

Ref	Description	Qty	Unit	Rate	Amount
	<u>SERIES 2600: MISCELLANEOUS</u>				
	Information Panels				
1	Display Panel Sign, A1 size, to be constructed from recycled plastic as per image below. To be placed into ST2 450mm deep concrete foundation, location* to be agreed with Engineer, as supplied by Murrays Recycled Plastic or equivalent 	1	No.	€ _____	€ _____
	Gates and Gate Posts				
2	12 ft D9 Sheep gates complete with galvanised hanging gate posts and closing gate posts as per image below. Gate posts to be set in concrete. 	4	No.	€ _____	€ _____
3	6 ft galvanised field gate with galvanised hanging gate post and closing gate post as per image below. Gate posts to be set in concrete. 	1	No.	€ _____	€ _____
Series 600 Total					

Ref	Description	Qty	Unit	Rate	Amount
4	Fencing Supply and installation of sheep fencing in accordance with the Department of Agriculture, Food and Marine S 148 Minimum specification for farm fencing. See image below 	3600.0	m	€ _____	€ _____
Page Total					

Ref	Description	Qty	Unit	Rate	Amount
	<u>SERIES 2600: MISCELLANEOUS - SUMMARY</u>				
	Page : 9				€ _____
	Page : 10				€ _____
Page Total					

Ref	Description	Qty	Unit	Rate	Amount
	SERIES 100 PRELIMINARIES SERIES 200 SITE CLEARANCE SERIES 500 DRAINAGE AND SERVICE DUCTS SERIES 700 & 900 PAVEMENTS - BITUMINOUS BOUND MATERIALS SERIES 2600 MISCELLANEOUS				
					€ _____
					€ _____
					€ _____
					€ _____
					€ _____
TOTAL TO BILL SUMMARY					

Bill Summary

		Amount
	Sub Bill Summary Total (exclusive of VAT)	€
	Adjustment Item (optional)	€
	Total excluding VAT (Transfer to Volume B - Tender & Schedule)	€
	Add VAT @ 13.5%	€
	Total including VAT	€



Comhairle Contae Mhaigh Eo
Mayo County Council



Contractor Details:

Contractor Name: Contractor Address: Contact Details: Contractors Signature:	
	Phone: _____ Mobile: _____ E-Mail: _____