




2 Ground Floor Lvl
1 : 50

INTERNAL WALL TYPES LEGEND

N.B. Tanking required to WC and Main Bathroom wall and floors



3 Wall Types
1 : 10



1 First Floor Lvl
1 : 50

KEYNOTE LEGEND2	
Key Value	Keynote Text
01.	Replacing roof tiles - Selected concrete roof tile, clipped and nailed on every row, on 35 x 44mm tiling battens. (To match existing.)
02.	Install eaves ventilation tray to maintain ventilation space to attic between insulation & roof membrane.
03.	Mechanical Air Extract Exhaust Through Roof Vent Tile
04.	Two roof vent tiles to be provided and front and rear. (Total : 4 no.)
05.	Replacing felt and battens and fireproofing on party wall and soffit box.
06.	Replacement of gable ladders and four roof trusses.
07.	Allow Up To 1.0m For The Making Good/Replacement Of Tiles, Timber Battens, Roof Membrane, Soffit/Fascia, Gutters, Downpipes to third party property.
08.	Splicing the end of all rafters for new black facia and soffit board. Refer to DWG 3001 Detail 07 Spliced Rafter Detail.
09.	Replacing valley timber.
10.	New Black uPVC Facia, soffit, downpipes and gutters with Dry Verge System to gable.
18.	New windows (RAL 7015) & doors (3no door colour finishes to be provided.)
19.	25mm insulated plasterboard reveal of all windows and doors. New airtightness tape and membrane to all window and door opes.
20.	New ESB Box and Eircom Box and EV Charger supply point (Shown on M&E Layouts.).
21.	Cut expansion joint at front, rear and side gable walls to install Helifix bar at 450 vertical centres at each side of the expansion joint.
25.	Centralised mechanical extract ventilation. Passive wall vent - TL100DE to each room.
27.	Chimney to be blocked up and taken down to below roof level.
28.	Replace all ceiling at GF = Ground Floor - 15mm plasterboard sheets & skimmed.
29.	Replace all ceiling at FF = First Floor - 15mm plasterboard sheets & skimmed.
31.	Insulating stud wall in bathroom
32.	New 18mm OSB3 tongue and groove flooring. Use 18mm Moisture resistant board in bathrooms
33.	New internal doors and architrave and skirting.
34.	New window boards to all windows.
35.	New Sanitary Fittings
36.	New kitchen units
38.	Replace footpath
40.	Replace driveway
41.	Boundary fence walls to rear and side (1.8m) and front sides (1.2m)
42.	3 coats of paint to external walls. Include for power washing and moss treatment.
44.	Attic hatch door must be airtight with isolation. (Stira or similar approved.)
45.	All proposed new walls that are a shared boundary with a privately occupied house should note subject to agreement with neighbour.
46.	Contractor to allow for Smith & Locke Post Box Black Powder-Coated.

3 BEDROOM / 5 PERSON HOUSE					
RELEVANT AREA	PROPOSED UNIT ACTUAL WIDTH	ACTUAL AREA (M²)	DEPT. GUIDELINES MIN. WIDTH	MIN. FLOOR AREA(M²)	COMPARISON OF FLOOR AREA %
Bedroom 1	3.1	13.8	2.8	13.0	105.1
Bedroom 2	3.1	11.4	2.8	11.4	100
Bedroom 3	2.4	7.8	2.1	7.1	109.8
Living Room	4.4	25.6	3.6	13.0	196.9
TOTAL STORAGE AREA	2.6		5	70	
TOTAL LIVING / KITCHEN / DINING	34		30	113.3	
GROSS INTERNAL AREA	105.2		92	114.6	

3 Bedroom / 5 Person House (Building Regulations)

- 92 sqm target floor area
- 13 sqm main living room (min 3.6m width)
- 34 sqm aggregate living area
- 32 sqm aggregate bedroom area
- 5 sqm storage
- 7.1 sqm single bedroom (min 2.1m width)
- 13 sqm main bedroom (min 2.8m width)
- 11.4 sqm double bedroom (min 2.8m width)

ROOM SCHEDULE - UNIT 01		
Name	Area	
GF Lvl		
Circulation	9.0 m²	
Kitchen/Dining	19.6 m²	
Living Room	19.2 m²	
Storage	1.7 m²	
WC	3.2 m²	
FF Lvl		
Bathroom	5.9 m²	
Bedroom 1	15.6 m²	
Bedroom 2	11.7 m²	
Bedroom 3	7.4 m²	
Circulation	10.4 m²	
Storage	1.6 m²	
	105.2 m²	

Note:
 Use figured dimensions only: do not scale drawings -Read in conjunction with specification and consultant's drawings -Report any discrepancies in drawings to architect and obtain instructions before putting work in hands -Check all dimensions on site. This drawing is copyright © 2024 of TA Group, Corrahoor, Kiltimagh, Mayo, and may not be reproduced, in whole or part, without TA Group prior consent.

No	Date	Description	Issued by	Issued to
00	26.03.2026	Tender Issue	CE	All

TA GROUP Roscommon County Council

Project: Shannon Valley - House Type 03
 Client: Roscommon County Council
 Sheet: HT03A-Floor Layouts (No. 39)

Date: 10/22/25
 Dwg No: 25020-X-HT03A-X-X-DR-TA-AR-1001

Project number: 25020
 Scale: As indicated
 Rev: 00

Accept Code: S
 Purpose Code: P1