

Dernafanogy Bridge, Donegal

Volume C: Pricing Document

24200-DID-ZZ-XX-BQ-C-4001

Document Details

Project:	Dernafanogy Bridge, Donegal		
Title:	Pricing Document		
External Project Number:	N/A		
Document Reference:	24200–DID–ZZ–XX–BQ–C–4001		
Design ID Project Number:	24200		
Date:	June 2026		
Current revision:	P03		
Suitability:	D2		
Suitability Description:	Issued for Tender		
Design Engineer:	Mark Rooney	Initial:	MR
Checking Engineer:	Ronan Carlin	Initial:	RC

Revision	Description	Date Revised	Revised By	Checked By
P01	Tender Issue	01.06.2026	MR	RC
P02	Tender Issue	19.06.2026	YH	RC
P03	Tender Issue	10.07.2026	YH	RC

© Copyright Design ID

This document has been prepared for the titled project or named part thereof and should not be relied upon or used for any other project without an independent check being carried out as to its suitability and prior written authority of Design ID being obtained. Design ID accepts no responsibility or liability for the consequence of this document being used for a purpose other than the purposes for which it was commissioned. Any person using or relying on the document for such other purpose agrees, and will by such use or reliance be taken to confirm his agreement to indemnify Design ID for all loss or damage resulting there from. Design ID accepts no responsibility or liability for this document to any party other the person for whom it was commissioned.

Item	Description	Unit	Quantity	Rate	Amount €
	CC-RMP-00100 Preliminaries				
	Temporary Accommodation				
1	Provision and erection of offices and messes for the Contractor.	item	1		€ -
2	Provision and erection of stores and workshops for the Contractor.	item	1		€ -
3	Servicing of offices and messes for the Contractor.	item	1		€ -
4	Servicing of stores and workshops for the Contractor.	item	1		€ -
5	Dismantling of offices and messes for the Contractor.	item	1		€ -
6	Dismantling of stores and workshops for the Contractor.	item	1		€ -
	Traffic Safety and Management				
7	Traffic Safety and Management as per Appendix 1/17.	item	1		€ -
8	Temporary Diversions for Traffic as per Appendix 1/18.	item	1		€ -
	Progress Photographs				
9	Provide progress photographs as described in Appendix 1/22.	item	1		€ -
	Project Supervisor for the Construction Stage				
10	Acceptance of Appointment as Project Supervisor for the Construction Stage. This item is to include for all Contractor Supervision for the works.	item	1		€ -
	Supplier Design				
	<i>Design & Detailing in accordance with Appendix 1/75, of the following:</i>				
11	Precast 300mm box beams and edge box beams.	item	1		€ -
	Safety File				
12	In accordance CC-RMP-00010.	item	1		€ -
	As Built Records				
13	As built records as per Appendix 1/75 of the specification.	item	1		€ -
	TOTAL PAGE 1				€ -

Item	Description	Unit	Quantity	Rate	Amount €
	CC-RMP-00100 Preliminaries				
	Waste Management Plan				
14	Provision of Waste Management Plan.	item	1		€ -
	Protection of Water Quality				
15	Measures to ensure protection of water quality, watercourse and neighbouring SACs/SPAs.	item	1		€ -
	Protection of Existing Works				
16	Protection of existing structures and provision of records for structures uncovered.	item	1		€ -
	Temporary Works				
17	Design of all necessary temporary works in accordance with Appendix 1/11.	item	1		€ -
18	Provision, installation and supervision of all temporary works required to construct the proposed works.	item	1		€ -
19	Taking measures for the design, construction, maintenance and removal of temporary access construction platforms as Appendix 1/11 of the Specification.	item	1		€ -
	TOTAL PAGE 2				€ -

	Description	Unit	Quantity	Rate	Amount €
	CC-RMP-00100 Preliminaries				
	Statutory Authority Liaison				
20	Donegal County Council Liaison to Appendix 1/72.	item	1		€ -
	Working and Fabrication Drawings				
21	Provision in accordance with Appendix 1/4.	item	1		€ -
	Testing				
22	Testing to Appendix 1/5.	item	1		€ -
	Facilities for Service Undertakers and Other Contractors				
23	Protection of Buried Services.	item	1		€ -
24	Consultation and Liaison with landowners prior to entering land.	item	1		€ -
	TOTAL PAGE 3				€ -
	TOTAL SERIES 00100 - PRELIMINARIES	To Grand Summary			€ -

Item	Description	Unit	Quantity	Rate	Amount €
	CC-RMP-00200 Site Clearance				
	Site Clearance				
1	General Site Clearance. Include for removal of vegetation and litter within site area. Refer to Appendix 2/70 for further information on vegetation removal.	ha	0.1		€ -
	Take up or down and remove to tip off site				
2	Remove existing asphalt surfacing over bridge deck to expose the concrete slab (no damage to slab).	m ²	50		€ -
3	Excavate and remove granular/sub-base over slab (within parapets).	m ³	13		€ -
4	Remove asphalt verge surfacing at bridge.	m ²	10		€ -
5	Plane-out approach carriageway for resurfacing.	m ²	100		€ -
6	Perimeter saw-cut to plane-out area, incl. making good edges.	m	50		€ -
7	Clean down parapet inner faces and deck margins (scrape vegetation/silt; prepare to receive grout/waterproofing). No stone removal.	m ²	15		€ -
8	Temporary removal & reinstatement of barbed-wire fence panels for access, incl. posts where required.	m	10		€ -
9	Cart-away and disposal of arisings (bituminous + granular) to licensed tip; include loading/haul.	m ³	25		€ -
10	Retain suitable arisings for reuse on site; stockpile/cover; compliance with Appendix 2/3.	item	1		€ -
	TOTAL SERIES 00200 - SITE CLEARANCE	To Grand Summary			€ -

Item	Description	Unit	Quantity	Rate	Amount €
	CC-RMP-00300 Fencing and Environmental Noise Barriers				
	Fencing				
1	Provision and installation of temporary fencing as required to provide a secure construction site / compound.	unit	1		€ -
	TOTAL SERIES 00300 - FENCING AND ENV. NOISE BARRIERS	To Grand Summary			€ -

Item	Description	Unit	Quantity	Rate	Amount €
	CC-RMP-00600 Earthworks				
	<i>Note: All excavation, disposal, fill and compaction works are to be undertaken strictly in accordance with the requirements of Appendix 6/1, 6/2, 6/3 and 6/6.</i>				
	Excavation of Sub-Base				
1	Excavation to formation for verge/path shoulders at bridge approaches; trim to line/level; protect existing.	m ³	10.0		€ -
	New Material				
2	Geotextile separator/barrier, 2 mm thick × 2.0 m wide, under verge/path build-up; overlaps	m ²	10		€ -
4	Capping 6F5 250mm	m ³	2		€ -
5	Granular regulating layer Class 6B, 50 mm beneath verge/path	m ³	1		€ -
6	Fill to structures / shoulders Class 6N, variable depth to tie-in.	m ³	2		€ -
7	Compaction of imported 6N / 6F5 / Type 3	m ³	5		€ -
	Hard Material				
8	Extra over for excavation in hard material.	m ³	1.0		€ -
	Disposal				
9	Dispose of unacceptable (Class U2/U1B) arisings to licensed tip; include loading/haul;	m ³	1		€ -
	Other				
10	Temporary drainage / sump pumping to keep formation dry	item	1		€ -
11	Environmental controls: sediment traps, spill kits, dust barriers, etc.	item	1		€ -
	TOTAL SERIES 00600 - EARTHWORKS	Total			€ -

Item	Description	Unit	Quantity	Rate	Amount €
	CC-RMP-00700 Pavements				
	Bridge Deck				
1	Deck binder course: AC20 Dense 40/60 des, 55 mm (SHW 900 Cl.906). Lay over approved waterproofing	m ²	50		€ -
2	Surface Course: 45mm AC14 dense 70/100 surface course, (MCHW SHW series 900, clause 906)	m ²	50		€ -
3	Approach Inlay Binder: 55mm AC20 dense 40/60 binder course (MCHW SHW series 900, clause 906)	m ²	100		€ -
4	Approach inlay – surface: 45mm AC14 Close Surf 70/100 dense (MCHW SHW series 900, clause 906)	m ²	100		€ -
5	Tack/bond coat beneath all new asphalt (deck+approaches).	m ²	165		€ -
6	Transverse road joints each side of deck to Detail B: saw-cut, prep, reinstate, seal.	m ²	15		€ -
7	Provisional full-depth patching: remove to base, reinstate AC32 Dense 100 mm + binder + surface (as above).	m ²	10		€ -
8	Cold Milling (Planing) - Tie into existing surface. Refer to Appendix 7/2.	m ²	10		€ -
	TOTAL SERIES 00700 - PAVEMENTS	To Grand Summary			€ -

8 / 13

Item	Description	Unit	Quantity	Rate	Amount €
	CC-RMP-02000 Waterproofing for Structures				
	Surface Impregnation and Coatings of Concrete				
1	Bridge Deck: Sika® Ergodur® epoxy overlay and Sikalastic® liquid applied membrane or similar approved, in accordance with Appendix 20/1.	m ²	65		€ -
2	Abutment Wall Extension: 2 No. Coats of bituminous waterproofing to buried concrete surfaces, Fosroc Mulseal DP (or similar approved), in accordance with Appendix 20/1.	m ²	20		€ -
TOTAL SERIES 02000 - WATERPROOFING		To Grand Summary			€ -

Item	Description	Unit	Quantity	Rate	Amount €
	CC-RMP-01700 Structural Concrete				
	Precast Concrete & Seating				
1	Supply and installation of precast Concrete, C40/50 precast 300mm depth box beams in accordance with Contract Drawings in Appendix 0/4, inclusive of required finishes as defined in Appendix 17/3.	No.	5.0		€ -
2	Supply and installation of precast Concrete, C40/50 precast 300mm edge box beams in accordance with Contract Drawings in Appendix 0/4, inclusive of required finishes as defined in Appendix 17/3.	No.	2.0		€ -
	Grout Works				
3	Grout below beams shall be high-flow, non-shrink, beam seating grout (Conbextra GP or similar approved), min 50 mm thickness.	m ³	1.0		€ -
4	Grout below bank seats shall be high-flow, non-shrink, beam seating grout (Conbextra HP or similar approved), min 50 mm.	m ³	1.0		€ -
	Cast In-Situ Concrete (Refer to Appendix 17/1 for Mix)				
5	Compressible levelling layer over existing slab, returned up inner parapet faces; provide proprietary compressible void former/levelling system capable of accommodating beam deflection without transferring structural load to the existing bridge deck, nominal 50 mm thick (final thickness to be confirmed based on appointed Precast Beam Supplier's design).	m ³	3.0		€ -
6	In-Situ Concrete fill for abutment, on each end of bridge, as per Appendix 17/1. This estimate is subject to existing abutment extent and is therefore conservatively factored by 1.3	m ³	5.0		€ -
	Steel Reinforcement & Formwork				
6	Steel Bar Reinforcement for Precast Concrete box edge beams - Contractor Designed Element per Appendix 17/1. Estimate of steel tonnage only.	t	0.5		€ -
7	Steel Bar Reinforcement for Precast Concrete box Beams - Contractor Designed Element per Appendix 17/1. Estimate of steel tonnage only.	t	1.1		€ -
8	Formwork to vertical faces (Class F4 finish) for bank seats.	m ²	20.0		€ -
	Execution, Finishes, Curing & Quality Assurance				
9	Surface finish to formed concrete: Class F4 where exposed; F2 where hidden; unformed U3/U2 as applicable; includes rubbing up/defect rectification.	m ²	20.0		€ -
TOTAL SERIES 01700 - STRUCTURAL CONCRETE		To Grand Summary			€ -

Item	Description	Unit	Quantity	Rate	Amount €
	CC-RMP-02300 Bridge Expansion Joints and Sealing of Gaps				
	Expansion Joints				
1	Provision and installation of expansion joints in accordance with Appendix 23/2.	m	11.0		€ -
	Sealing of Gaps				
2	Edge chases / minor surface discontinuities adjacent to parapet returns and deck edges, prior to waterproofing. Clean, pre-wet as required; grout flush and finish.	m ³	0.2		€ -
3	Interface gap sealing – transverse deck ends. Same grout and requirements, sealing at both tie-in ends across deck width.	m ³	0.1		€ -
4	Local voids/pockets at beam ends and seat transitions. Grout small voids/honeycombing arising at precast end faces, bearing seat arrises and compressive layer returns. Shutter as needed.	m ³	0.1		€ -
5	Edge chases / minor surface discontinuities adjacent to parapet returns and deck edges, prior to waterproofing. Clean, pre-wet as required; grout flush and finish.	m ³	0.1		€ -
6	Temporary formwork & containment (stop-ends, fillet forms, seals), install/remove; surfaces cleaned ready for waterproofing.	item	1		€ -
	TOTAL SERIES 02300 - BRIDGE EXPANSION JOINTS & SEALING OF GAPS	To Grand Summary			€ -

Item	Description	Unit	Quantity	Rate	Amount €
	CC-RMP-02400 Brickwork, Blockwork and Stonework				
	Stonework; sandstone; random rubble; cement mortar in accordance with Specification, Appendix 4/1 and 24/1				
	Bridge 1				
1	Construct new cut-stone masonry parapets both sides of deck to extend existing parapet to 1.25m height, as per Appendix 24/1	m ³	1.10		€ -
2	Supply and install precast copings along both parapets of new deck, as per Appendix 24/1	m	16		€ -
	TOTAL SERIES 02400 - BRICK, BLOCK AND STONWORK	To Grand Summary			€ -

Item	Description				
	Grand Summary				
	Series Sub-Totals		Euro (€)		
1	CC-RMP-00100 Preliminaries		€0		
2	CC-RMP-00200 Site Clearance		€0		
3	CC-RMP-00300 Fencing and Environmental Noise Barriers		€0		
4	CC-RMP-00600 Earthworks		€0		
5	CC-RMP-00700 Pavements		€0		
6	CC-RMP-01100 Kerbs, Footways and Paved		€0		
7	CC-RMP-01700 Structural Concrete		€0		
8	CC-RMP-02000 Waterproofing		€0		
9	CC-RMP-02300 Bridge Expansion Joints and Sealing of Gaps		€0		
	Total:		€ 0		