

Bill of Addendum

Project: CETB Biomass - Heating Upgrade Works
Building: Carrigaline Community College

Details: Bill of Addendum Nr 1

Autoc ode	Description	Quantity	Unit	Rate	Total
1	BILL OF ADDENDUM NR 1				
	(MECHANICAL BOQ)				
	ENERGY CABIN CIVIL & SITE WORKS		Head 1		
	xxADDxx				
1.A	Supply and install draw chambers, 1000 × 1000 mm internal size, complete with excavation, concrete base, precast chamber sections, duct openings, cover and frame, backfilling, disposal of surplus material, reinstatement and all ancillary works in accordance with Fingleton Whites drawings and specification	3	Nr		
1.B	^^^BoQ item 3: ". Description Change: From: Trenching for underground services, including excavation, bedding, backfill and reinstatement To: Trenching for underground services, including excavation, supply and installation of ducting, bedding, backfilling, reinstatement and all ancillary works, complete in accordance with the drawings and specification	1	item		
	(ELECTRICAL BOQ)				
	xxOMITxx				
1.C	^^^BoQ item 12: ". Underground ducting and external trenching works excluded unless otherwise stated."	-1	item		
1.D	^^^BoQ item 19: ". Description Change: From: "Supply and install cable containment systems for new LV and ELV cabling including cable tray, cable ladder, trunking, conduits, supports, brackets and fixings complete, excluding underground ducting (by others)." To: "Supply and install cable containment systems for new LV and ELV cabling including cable tray, cable ladder, trunking, conduits, supports, brackets and fixings complete"	-1	item		
	(PRELIMINARIES BOQ)				
	xxADDxx				
1.E	The Contractor shall coordinate with the separately appointed Biomass Contractor and individual school authorities for site access and completion of all works: (refer to Master Project Information Memorandum (PIM) – REV 1)	1	Item		
1.F	Heating must be available to all schools by no later than 01 October 2026; therefore, should the new heating system as part of the Works not be fully operational before this date, the Tenderer must provide all temporary equipment required to provide heating to the schools until the newly installed heating systems are commissioned; (refer to Master Project Information Memorandum (PIM) – REV 1)	1	Item		
1.G	The Contractor shall be responsible for mobilisation and demobilisation between all works phases: (refer to Master Project Information Memorandum (PIM) – REV 1)	1	Item		

BILL OF ADDENDUM NR 1

To Collection:

Bill of Addendum

Project: CETB Biomass - Heating Upgrade Works	Details: Bill of Addendum Nr 1
Building: Carrigaline Community College	

Autoc ode	Description	Quantity	Unit	Rate	Total
1	BILL OF ADDENDUM NR 1				(Continued)

COLLECTION

Page 1:

BILL OF ADDENDUM NR 1
Carried to Summary:

--

Project: CETB Biomass - Heating Upgrade Works	Details: Bill of Addendum Nr 1
Building: Carrigaline Community College	

Autoc ode	Description	Quantity	Unit	Rate	Total
--------------	-------------	----------	------	------	-------

COLLECTION SUMMARY

PAGE NO

BILL OF ADDENDUM NR 1
Total Amount:

1