

Client		Donegal County Council		Date	16/07/2026	
Scope		Pricing Document		Prepared by	AMcD	
Project		Meenreagh Bridges Rehabilitation, Killygordon, Co. Donegal		Checked by	JL	
Job No./ Ref.		25076		Register Rev	TN01	
ITEM	DESCRIPTION	QUANTITY	UNIT	RATE € (Excl. VAT)	TOTAL COST € (Excl. VAT)	
PART 1						
S100	Preliminaries					
	Temporary Accomadation					
1.100.01	Erection of stores and messes for the contractor & removal on completeion	1	Item		€0.00	
	Traffic Safety and Management					
1.100.02	Local Road - Traffic Safety and Management, including stop/go or signage for temporary diversion of traffic should it be required	1	Item		€0.00	
	Liaison with IFI/LA					
1.100.03	Provide method statement to IFI/LA and ensure approval of works is agreed prior to carrying out of works in or near the watercourse.	1	Item		€0.00	
	Progress Photos					
1.100.04	Daily set of progress photographs in colour and in electronic format	1	Item		€0.00	
	Facilities for Local Authority, Public or Private Utility Undertakers and Other Contractors					
1.100.05	Facilities for Donegal County Council	1	Item		€0.00	
1.100.06	Facilities for Adjoining Landowners	1	Item		€0.00	
1.100.07	Facilities for Inland Fisheries	1	Item		€0.00	
	Acceptance of Appointment of Project Supervisor Construction Stage					
1.100.08	Acceptance of appointment of Project Supervisor for the Construction Stage	1	Item		€0.00	
	Emergency Services					
1.100.09	Emergency Services	1	Item		€0.00	
	Road Sweeping & Cleaning					
1.100.10	Road Sweeping & Cleaning	1	Item		€0.00	
	Insurances					
1.100.11	Contractor to provide the insurances defined in the contract documents.	1	Item		€0.00	
	Temporary Works					
1.100.12	Temporary access for works to bridge	1	Item		€0.00	
1.100.13	Protection of existing services	1	Item		€0.00	
1.100.14	Protection of water quality	1	Item		€0.00	
	Environmental Considerations					
1.100.15	Adherence to the Recommendations set out in the AA Screening Report	1	Item		€0.00	
	Jet wash					
1.100.15	Jet wash both bridge structures to remove friable material and wire brush where required in preperation for construction works.	1	Item		€0.00	
PART 1 TOTAL					€0.00	

ITEM	DESCRIPTION	QUANTITY	UNIT	RATE € (Excl. VAT)	TOTAL COST € (Excl. VAT)
	PART 2				
S200	Site Clearance				
2.200.01	General Site Clearance to allow works to be carried out safely	1	Item		€0.00
	Take Up or Down and Set Aside for Reuse or Remove to Store or Tip Off Site				
2.200.02	Extents of Demolition works as per drawing 1104 - Meenreagh Bridge 1	1	nr		€0.00
				PART 2 TOTAL	€0.00
	PART 4				
S600	EARTHWORKS				
	EXCAVATION				
4.600.01	Excavation of material	18	m3		€0.00
	DISPOSAL OF MATERIAL				
4.600.02	Disposal of unacceptable material Class U1 off site	18	m3		€0.00
				PART 4 TOTAL	€0.00
	PART 5				
S700	PAVEMENTS				
	SUB BASE				
5.700.01	Granular type B Cl 804 sub base, 150mm thick	8	m3		€0.00
	BINDER COURSE				
5.700.02	Asphalt concrete dense binder, aggregate size 20mm, 75mm thick	70	m2		€0.00
	SURFACE COURSE				
5.700.03	Hot Rolled Asphalt course, to CL.911, aggregate size 14mm, 50mm thick	70	m2		€0.00
	DOUBLE SURFACE DRESSING				
5.700.04	Double Surface dressing as RCD/700/6	140	m2		€0.00
	BOND COAT				
5.700.05	Bond coat	70	m2		€0.00
	TRANSVERSE JOINT BETWEEN NEW AND EXISTING ROAD				
5.700.06	Form transverse joint between new road construction and existing road as in accordance with RCD/700/3	9	m		€0.00
				PART 5 TOTAL	€0.00
	PART 6				
S1200	TRAFFIC SIGNS AND ROAD MARKINGS				
6.1200.01	Provide new Road narrowing definition posts as per TII CC SCD 01204 Sign to be fixed to 60 x5 galvanised pole complete with associated fixings and 500sq x 500mm deep footing use ST4 concrete mix	4	No		€0.00
				PART 6 TOTAL	€0.00
ITEM	DESCRIPTION	QUANTITY	UNIT	RATE € (Excl. VAT)	TOTAL COST € (Excl. VAT)
	PART 7				
S1700	STRUCTURAL CONCRETE				
	BEARING SLAB & Rubbing strip				
	In Situ Concrete				
7.1700.01	In situ concrete, grade C35/45; surface finish to SPW 1100 -	3	m3		€0.00
7.1700.02	In situ concrete, grade C30/37; surface finish to SPW 1100-	0.3	m3		€0.00
	Steel Reinforcement for Structures				
7.1700.03	A393 reinforcement mesh to BS 4483, provided top and bottom cover = 50mm	25	m2		€0.00

	Formwork				
7.1700.04	Formwork, vertical, F4 finish	18	m2		€0.00
7.1700.05	250-500mm high formwork for edges	17.6	m		€0.00
7.1700.06	Form 50mm chamfer to rubbing strip edge	8.8	m		€0.00
	INSITU CONCRETE BRIDGE DECK				
7.1700.07	Formwork, F4 finish	17	m2		€0.00
7.1700.08	250-500mm high formwork for edges	10	m		€0.00
7.1700.09	Grade B500B steel bar reinforcement deformed type 2 bars nominal size as per Rebar Schedule	1.3	T		€0.00
7.1700.10	In Situ concrete, grade C35/45 to form new Deck slab	7.5	m3		€0.00
	Allow for all propping, setting out and all associated works.	1	Item		€0.00
	Allow for all attendances, liaison with specialist and erection attendances	1	Item		€0.00
	Allow for all pumps, plant and equipment required for bridge widening.	1	Item		€0.00
7.1700.11	2 No of 50mm diameter ducts for future services - location to be coordinated on site with client	16	m		€0.00
	INSITU PARAPET WALLS				
7.1700.12	Formwork, F4 finish	23	m2		€0.00
ITEM	DESCRIPTION	QUANTITY	UNIT	RATE € (Excl. VAT)	TOTAL COST € (Excl. VAT)
7.1700.13	Grade B500B steel bar reinforcement deformed type 2 bars nominal size as per Rebar Schedule	0.8	T		€0.00
7.1700.14	In Situ concrete, grade C40/50 to form new Parapet Walls	3	m3		€0.00
	Allow for all propping, setting out and all associated works.	1	Item		€0.00
	Allow for all attendances, liaison with specialist and erection attendances	1	Item		€0.00
	Allow for all pumps, plant and equipment required for bridge widening.	1	Item		€0.00
7.1700.15	Form 40mm chamfer to top of parapet walls	18	m		€0.00
				PART 7 TOTAL	€0.00
	PART 8				
S2000	WATERPROOFING OF STRUCTURES				
8.2000.01	Sikalastic-851 or Equivalent approved	17	m2		€0.00
				PART 8 TOTAL	€0.00
	PART 9				
S2400	BRICKWORK, BLOCKWORK AND STONEMWORK				
	MASONARY WING WALLS				
	Remove from Store and Relay Stonework				
9.2400.01	Existing section of Masonary Wingwalls to be demolished and Reconstructed to match existing on upstream and downstream elevation	6	m2		€0.00
9.2400.02	Rake out and repoint existig masonry wingwalls and abutments	24	m2		€0.00
	Allow for all propping, setting out and all associated works.	1	Item		€0.00
	Allow for all attendances, liaison with specialist and erection attendances	1	Item		€0.00
	Allow for all pumps, plant and equipment required for bridge widening.	1	Item		€0.00
				PART 9 TOTAL	€0.00

[illegible]

7.1700.03	A393 reinforcement mesh to BS 4483, provided top and bottom cover = 50mm	25	m2		€0.00
	Formwork				
7.1700.04	Formwork, vertical, F4 finish	22.94	m2		€0.00
7.1700.05	250-500mm high formwork for edges	18	m		€0.00
7.1700.06	Form 50mm chamfer to rubbing strip edge	13	m		
	INSITU CONCRETE BRIDGE DECK				
7.1700.07	Formwork, F4 finish	22.94	m2		€0.00
7.1700.08	250-500mm high formwork for edges	13	m		€0.00
7.1700.09	Grade B500B steel bar reinforcement deformed type 2 bars nominal size as per Rebar Schedule	1.7	T		€0.00
7.1700.10	In Situ concrete, grade C40/50 to form new Deck slab	9.3	m3		€0.00
	Allow for all propping, setting out and all associated works.	1	Item		€0.00
	Allow for all attendances, liaison with specialist and erection attendances	1	Item		€0.00
	Allow for all pumps, plant and equipment required for bridge widening.	1	Item		€0.00
7.1700.11	2 No of 50mm diameter ducts for future services - location to be coordinated on site with client	16	m		€0.00
	INSITU PARAPET WALLS				
7.1700.12	Formwork, F4 finish	30	m2		€0.00
ITEM	DESCRIPTION	QUANTITY	UNIT	RATE € (Excl. VAT)	TOTAL COST € (Excl. VAT)
7.1700.13	Grade B500B steel bar reinforcement deformed type 2 bars nominal size as per Rebar Schedule	1.1	T		€0.00
7.1700.14	In Situ concrete, grade C40/50 to form new Parapet Walls	3.6	m3		€0.00
	Allow for all propping, setting out and all associated works.	1	Item		€0.00
	Allow for all attendances, liaison with specialist and erection attendances	1	Item		€0.00
	Allow for all pumps, plant and equipment required for bridge widening.	1	Item		€0.00
				PART 14 TOTAL	€0.00
	PART 15				
S2000	WATERPROOFING OF STRUCTURES				
8.2000.01	Sikalastic-851 or Equivalent approved	22	m2		€0.00
				PART 15 TOTAL	€0.00
	PART 16				
S2400	BRICKWORK, BLOCKWORK AND STONEMWORK				
	MASONARY WING WALLS				
	Remove from Store and Relay Stonework				
9.2400.01	Existing section of Masonary Wingwalls to be demolished and Reconstructed to match existing on upstream and downstream elevation	6	m2		€0.00
9.2400.02	Rake out and repoint existing masonry wingwalls and abutments	25	m2		€0.00
	Allow for all propping, setting out and all associated works.	1	Item		€0.00
	Allow for all attendances, liaison with specialist and erection attendances	1	Item		€0.00
	Allow for all pumps, plant and equipment required for bridge widening.	1	Item		€0.00
				PART 16 TOTAL	€0.00

ITEM	DESCRIPTION	QUANTITY	UNIT	RATE € (Excl. VAT)	TOTAL COST € (Excl. VAT)
	Part 1 - Preliminaries				€0.00
	Bridge 1				
	Part 2 - Site Clearance				€0.00
	Part 4 - Earthworks				€0.00
	Part 5 - Pavements				€0.00
	Part 6 - Traffic Signs & Markings				€0.00
	Part 7 - Structural Concrete				€0.00
	Part 8 - Waterproofing				€0.00
	Part 9 - Brickwork, Blockwork & Stonework				€0.00
	Bridge 2				
	Part 10 - Site Clearance				€0.00
	Part 11- Earthworks				€0.00
	Part 12 - Pavements				€0.00
	Part 13 - Traffic Signs & Markings				€0.00
	Part 14 - Structural Concrete				€0.00
	Part 15 - Waterproofing				€0.00
	Part 16 - Brickwork, Blockwork & Stonework				€0.00
TOTAL EXCL. VAT					€0.00

It is the Employers intention to retain the successful Tenderer to complete the wall restoration in its entirety based on the rates provided herein.
Contractor shall ensure all aspects of the Works as detailed in the Works Requirements are accounted for.

Signature of authorised person _____

Name in capitals _____

Title _____

Date _____

On behalf of:

Tenderer's name in full _____

Postal address _____

In the presence of:

Name of witness _____

Signature of witness _____

Witness's occupation _____

Witness's address _____