

- | Revisions | |
|-----------|--|
| | |




CONTRACTOR TO ALLOW FOR THE REMOVAL AND DISPOSAL OFF SITE TO AN AUTHORISED DUMP OF ALL THE EXISTING PANTILE ROOF TILES, TIMBER BATTENS, EXISTING SARKING FELT, LEAD FLASHINGS, FLAT VALLEY, FASCIA BOARDS AND GUTTERS AND DOWNPIPES ALL AS INDICATED ON THE ATTACHED DRAWINGS COLOURED BLUE AND CONTRACTOR TO ALLOW FOR THE CLEANING DOWN AND PREPARATION OF THE EXISTING PITCHED ROOF AREAS TO RECEIVE THE INSTALLATION OF NEW SELECTED ROOF FINISHES.

- CONTRACTOR TO ALLOW FOR CORE DRILLING OF NEW 52NO. 127MM DIA CORE THROUGH EXISTING EXTERNAL WALLS TO FACILITATE INSTALLATION OF NEW PERMANENTLY OPEN WALL VENTS TO ALL HABITABLE ROOMS.
- CENTRE OF CORE TO BE 50MM BELOW WINDOW HEAD HEIGHT AND MINIMUM 225MM FROM WINDOW REVEAL TO AVOID STRUCTURAL DAMAGE TO ALL WINDOW LINTELS.

EXISTING SCHOOL ENTRANCE AND SCHOOL ACCESS ROADWAYS TO HAVE SHARED ACCESS BETWEEN SCHOOL USERS AND CONTRACTORS. CONTRACTOR USE OF THIS ENTRANCE AND ACCESS ROADWAYS TO BE RESTRICTED TO USE BY THE CONTRACTOR OUTSIDE OF NORMAL SCHOOL 'DROP-OFF' AND 'PICK-UP' HOURS.

- CONTRACTOR TO ALLOW FOR THE SAFE REMOVAL AND SAFE STORAGE OF THE SCHOOLS SIGNAGE AND CREST AT LOCATIONS MARKED ON ELEVATIONS AND FOR THE REINSTATEMENT OF THE SCHOOLS SIGNAGE AND CREST ON COMPLETION OF THE WORKS TO THE SAME LOCATION.**



- KEY:**
-  ELECTRICS TO BE TEMPORARILY REMOVED
 -  CORE DRILL 100MM DIA OPE TO EXTERNAL WALLS FOR INSTALLATION OF NEW WALL VENTS
 -  HACK OFF EXISTING PLASTER BANDS TO FACILITATE NEW SIKA PLASTERING SYSTEM
 -  REMOVE ALL EXTERNAL RAINWATER GOODS, SVPS AND FACIA AND SOFFITS TO FACILITATE PLASTERING WORKS AND EXTENDING FACIA AND SOFFITS
 -  REMOVE ALL HANDRAILS TO STEPS THAT ARE FIXED TO EXTERNAL FACADE TO FACILITATE NEW SIKA PLASTERING SYSTEM

TENDER 

DEMOLITION / ALTERATION ELEVATIONS

SCALE: A1 @ 1:100 DATE: MAY 26 DRAWING NO.:
A3 @ 1:200 26-108-TR-03
© Copyright reserved to drawing and design.

