

## PRICING DOCUMENT

**Redevelopment of sports ground to include drainage, resurfacing and associated site works for St. Crone's National School, Chapel Road, Dungloe, Co. Donegal, F94 YV26.**

| Item | Description                                                                                                                                                                                                 | Unit           | Quantity | Rate | Total |
|------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|----------|------|-------|
| A    | <b>Preliminaries</b><br>Site establishment, setting out, signage, temporary fencing, Welfare Facilities, Insurance, Site security, Health and Safety Regulations                                            | Item           |          |      | €     |
| B    | <b>Site Clearance</b>                                                                                                                                                                                       |                |          |      |       |
| B1   | Remove Existing Goals, Store in agreed location and re-erect prior to pitch hand over                                                                                                                       | Item           |          |      | €     |
| B2   | Allow for stripping topsoil depth not exceeding 200mm deep from existing pitch and stockpiling on green area adjacent to site                                                                               | m <sup>2</sup> | 3,350    |      | €     |
| C    | <b>Drainage</b>                                                                                                                                                                                             |                |          |      |       |
| C1   | Allow for connection into Existing Main Collector drain                                                                                                                                                     | Item           |          |      | €     |
| C2   | Install Lateral Drains at 5mcentres throughout pitch and path areas using 100mm uPVC pipes laid @ 1@100 falls; Not exceeding 150mm wide x 450mm in depth. Include for backfilling with 10-20mm clean stone. | m              | 738      |      | €     |
| D    | <b>Running Track</b>                                                                                                                                                                                        |                |          |      |       |
| D1   | Form running track as indicated on site map, 3m wide, buildup with clean stone minimum 150mm deep and compact                                                                                               | m <sup>2</sup> | 630      |      | €     |
| D2   | Supply and lay 50mm quarry dust blinding to track and compact                                                                                                                                               | m <sup>2</sup> | 630      |      | €     |
| D3   | Supply and lay 150mm x 50 mm precast concrete Pencil kerb to outer edges of track, kerbs to be set on concrete base and haunch                                                                              | m              | 420      |      | €     |

|    |                                                                                                                                                                                                                                                                                             |                |                      |  |   |
|----|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|----------------------|--|---|
| E  | <b>Sand Dressing, Seeding, and Surface Aeration</b>                                                                                                                                                                                                                                         |                |                      |  |   |
| E1 | Supply and Spread Topdressing Sand mixed with stockpiled topsoil to entire pitch area (suitable sand to be supplied by contractor), not exceeding 200mm deep                                                                                                                                | m <sup>2</sup> | 2720                 |  | € |
| E2 | Seed and Fertilise Pitch                                                                                                                                                                                                                                                                    | Item           |                      |  | € |
| E3 | Verti Drain pitch                                                                                                                                                                                                                                                                           | Item           |                      |  | € |
| F  | <b>Miscellaneous Items</b><br>It is the contractor's responsibility where possible to itemise and include for items not specifically mentioned in the above elements.<br><br>No exclusions will be entertained.<br><br>All miscellaneous items shall be listed and priced separately below. |                |                      |  |   |
| F1 | Additional Items (if any):                                                                                                                                                                                                                                                                  |                |                      |  | € |
|    |                                                                                                                                                                                                                                                                                             |                | <b>SUB TOTAL</b>     |  | € |
|    |                                                                                                                                                                                                                                                                                             |                | <b>VAT @13.5%</b>    |  | € |
|    |                                                                                                                                                                                                                                                                                             |                | <b>OVERALL TOTAL</b> |  | € |