


1 Lighting Drawing
1 : 50



LIGHTING SERVICES LEGEND

	KSR Navara Pro Select model, KSR08100 P=20W, 2457 Lumen Colour Temperature 3000K
	KSR Roma Pro Select mod, KSR08400 P=14W, 1067 Lumen Colour Temperature 3000K
	WALL LIGHT
	STANDARD 6" DOMESTIC CEILING PENDANT
	Floodlights P=20W black led Colour Temperature 4000K with PIR
	ON-COUNTER KITCHEN LIGHTS
	EXTRACTOR FAN WITH TIMER
	CEILING SURFACE/ RECESSED 360° PRESENCE/ OCCUPANCY DETECTOR
	LIGHT SWITCH
	SINGLE POLE CHANGEOVER
	EXISTING FUSE BOARD LOCATION
	EXISTING OIL BOILER LOCATION
	HOT WATER CYLINDER

- NOTE:
- ALL ELECTRICAL SOCKET OUTLETS, FUSED SPUR OUTLETS, LIGHT SWITCHES ETC ARE TO BE FLUSHED MOUNTED.
 - UNDER NO CIRCUMSTANCES IS THE CONTRACTOR TO ORDER ANY MATERIALS FOR THE ELECTRICAL INSTALLATION BEFORE AGREEING QUANTITY AND MANUFACTURE WITH THE CONSULTING ENGINEER.
 - CONTRACTOR TO AGREE FINAL LOCATIONS OF ALL ITEMS IN THE ELECTRICAL SERVICES INSTALLATION WITH THE CONSULTING ENGINEER BEFORE INSTALLING SAME.
 - CONTRACTOR FOR REFER TO ELECTRICAL SPECIFICATION DOCUMENT FOR DETAILED EQUIPMENT SPECIFICATION.
 - THE CONTRACTOR IS REQUIRED TO REVIEW THE MECHANICAL DRAWINGS AND MAKE ALLOWANCES FOR ELECTRICAL CONNECTION OF ALL MECHANICAL EQUIPMENT.
 - THE FULL ELECTRICAL INSTALLATION SHALL BE CERTIFIED IN ACCORDANCE WITH I.S. 10101 WIRING REGULATIONS.
 - ALL ELECTRICAL EQUIPMENT TO BE INSTALLED TO MANUFACTURERS GUIDELINES.

CONTRACTORS TO VISIT SITE PRIOR TO TENDERING FOR WORKS TO ASCERTAIN THE EXTENT OF ALTERATIONS TO EXISTING SYSTEMS REQUIRED.
ALL WORKS TO BE CERTIFIED UPON COMPLETION



PROJECT
Carra Mor, Community Dwelling
Lifford,
Ennis, Co. Clare

TITLE
Electrical Lighting Drawing

CLIENT
Corlann - Clare Region

DRAWN BY Author	CHECKED BY Checker	DATE 07/29/26
SCALE (@ A1) 1 : 50	PROJECT NUMBER 24/BOC/081	
DRAWING NUMBER 26/D/0607		REV