Dermot O'KEEFFE & ASSOCIATES
Consulting Engineers

Bar schedule ref : 103 Rev

Site ref : Retaining Walls

Date prepared : 27-May-26

Job no : 1362 Sarsfield Barracks

Prepared by : JMD

Checked by : DOK

Member	Bar mark	Type and size	No. of mbrs	No. of bars in each	Total no.	Length of each bar † mm	Shape code	*A* * mm	*B* * mm	*C* * mm	*D* * mm	*E/R* * mm	Rev letter
250mm Thk. R.C. Wall	01	H 12	1	410	410	1275	21	200	900	200			
	02	H 10	1	47	47	12000	01	12000					
	03	H 12	1	410	410	1650	11	450	1200				
	04	H 12	1	410	410	1100	00	1100					
	05	H 10	1	205	205	925	21	400	150	400			
	06	H 10	1	63	63	12000	01	12000					
Corner bars	07	H 10	1	48	48	1200	11	600	600				
End bars	08	H 10	1	48	48	1350	21	600	170	600			

This schedule conforms to BS 8666:2005

Bar Schedule 8666 v5.02

* Specified in multiples of 5mm.

† Specified in multiples of 25mm.