

Coimisineir Teanga
An Spideál
Co. na Gaillimhe
Mechanical Scope of Works.
UNG-CT-SW-1

General Description of the works

The project includes for the disconnection, removal and replacement of the 3 No Airconditioning AHU units on the roof plant area of the building, including the associated ductwork, attenuators, fittings, weathered upstands etc.

The scope also includes modifications and additions to the existing ductwork installation on the ground floor to serve additional modular offices that were originally part of an open plan arrangement.

There will be an element of builderswork associated with removing and replacing the roof plant and the installation of the additional ducting within the ground floor office areas.

This document describes the broad scope of the works being carried out to meet these needs, please refer to the tender docs for the detailed requirements and specifications.

This document and the WIECS tender drawings must be read in conjunction with the client drawings, specifications and scope of works

Handover Documents

The contractor to allow for a full Safety file to include as a minimum a set of Operating and Maintenance documentation and record drawings when the work is complete.