

Proposed Playground at Knockmore Co Mayo

PRICING DOCUMENT - SUPPLY AND INSTALLATION OF PLAYGROUND

Item	Description	Quantity	Total
1	Insurances Health & Safety Including Independent Certification	Item	
2	Project Management & Supervision of works	Item	
3	Project Supervisor Construction Stage	Item	
4	Provision of all tools, plant and equipment required to complete the works in a safe manner	Item	
5	Site removal & ground preparation Strip topsoil where relevant, grade to required formation levels Any material removed from the proposed site shall be taken to a licensed facility (Transport vehicle shall have all valid licences, registrations, permit and all relevant documentation	Item	
6	Supply and install <u>Swing Collection</u> <u>Robinia Swing collection</u> Item 02 - Toddler swings Potentially including Flat Seat, Mirage seat or Cradle seat to Toddler swings (or similar approved / equivalent swings Collection) Item 09 - Flat seats & Basket Swing Double Combination swings Potentially Including Flat Seats + Basket Swing (or similar approved / equivalent swings Collection) Refer to Specification Sheets 01A, 01B, 01C <u>Refer to Item 02 + Item 09 on Drawing No. D_203-L(99)02 Indicative Playground Layout and Equipment</u> [Robina Swing collection or similar approved / equivalent swings]	Item	

Proposed Playground at Knockmore Co Mayo

7	Supply and install Springers Eurobina or similar approved / equivalent Springers Refer to Specification sheet 01D Refer to <u>Item 05</u> on Drawing No. D_203-L(99)02 Indicative Playground Layout and Equipment	2 Number	
8	Supply and install All Abilities Roundabout [All Abilities Roundabout – no restrictor – coastal coating – colour holly green] GL Jones roundabout or similar approved / equivalent roundabout / carousel may be considered Refer to Specification Sheet 01E Refer to <u>Item 08</u> on Drawing Number D_203-L(99)02 Indicative Playground Layout and Equipment	1 Number	
9	Supply and install Multi-play Unit - Junior Europlay (or similar approved/ equivalent multi play unit) Refer to Specification Sheets 01F Refer to <u>Item 04</u> on Drawing No. D_203-L(99)02 Indicative Playground Layout and Equipment	1 Number	
10	Supply and install Multi-play Unit - Senior Europlay (or similar approved/ equivalent multi play unit) Refer to Specification Sheets 01G Refer to <u>Item 04</u> on Drawing No. D_203-L(99)02 Indicative Playground Layout and Equipment		
11	Supply and install Adventure Trail Robinia Group (or similar approved/ equivalent adventure trail) Balance Beam, Stilts, Stepping Posts Refer to Specification Sheets 01H Refer to <u>Items 06 & 07</u> on Drawing No. D_203-L(99)02 Indicative Playground Layout and Equipment	1 Number	

Proposed Playground at Knockmore Co Mayo

12	Supply and install Single Cableway 30m Kaiser & Kuhne (or similar approved/ equivalent cableways) with Pendulum seat Refer to Specification Sheets 01I Refer to Item 01 on Drawing No. D_203-L(99)02 Indicative Playground Layout and Equipment		
13	Supply and install Safety Surfacing (Tiger mulch) Including for all associated civil works. Provide kerbing to safety zone. Prepare safety zone for safety surfacing and Tiger Mulch safety surfacing or similar approved / equivalent Safety surfacing may be considered Refer to Specification Sheet 01J	285 m ²	
14	Supply and install Safety surfacing (Grass mat rubber surfacing) (Including Mesh underlay) Refer to Specification Sheet 01K Grass mat rubber safety surfacing or similar approved / equivalent safety surfacing Please be advised that grass mat rubber surfacing shall <u>only</u> be placed on well established Roll out Grass Turf Surfacing	190 m ²	
15	Supply and install Playground rules and regulations Signage Signage shall be installed in accordance with manufactures instruction and all relevant standards Refer to Specification Sheet 01L	1 Number	
16	Supply and install Department acknowledge signage <u>Typical signage specification is as follows:</u> Sign face is 2.5mm aluminium, with a Class Ref 2 reflective face. Flat plate drilled for fixing to Galvanised steel post. Sign size 420 x 207mm (A3 size).	1 Number	

Proposed Playground at Knockmore Co Mayo

17	Supply & Install <u>Castit Limited Black Cannon cast metal litter bin</u> 75l with galvanised liner above ground 960mm, 400m diameter [Or similar approved/equivalent litter bin]	Item	
18	Supply and Install of <u>HARTECAST Seating</u> <u>HARTECAST Product item code: HC2026S</u> [Or similar approved/equivalent seating] <u>Refer to Items 10 & 11 on Drawing No. D_203-L(99)02 Indicative Playground Layout and Equipment</u>	3 Number	
19	Supply and Install PUBLIC LIGHTING & CCTV SYSTEM Supply and Install <u>Avigilon HD Video Appliance</u> [Or similar approved] Refer to Specification Sheet N Supply and Install <u>H4 HD Bullet Camera</u> [Or similar approved] Refer to Specification Sheet N Supply and Install <u>Axia 2.1 Lighting Standard</u> [Or similar approved] Refer to Specification Sheet O Supply and install 110mm Ducting for future <u>CCTV Cameras & Public Lights standards 6 m high</u> (Include for 12mm pull rope to be provided within ducting) Supply and install Duct Chambers Refer to : CONSTRUCTION DETAIL SHEET 01 - Typical Duct Chamber Detail Supply and install Lighting Pots / Chambers Refer to : CONSTRUCTION DETAIL SHEET 02 - Typical Public Light Pole Base Detail Refer to <u>Drawing No. D_203-L(99)01 Site Layout Plan</u>	53 Linear Meters Ducting Item 3 Number 3 Number 3 Number 3 Number 3 Number	
20	Access to playground [Accessible entrance] Ensure all gradient / fall to proposed playground entrance are in accordance with all building regulations and all relevant standards	Item	
21	Wheelchair Accessible Pathways Ensure all gradient / falls are in accordance with all building regulations and all relevant standards	Item	

Proposed Playground at Knockmore Co Mayo

22	Supply & Install Tarmac Surfacing 10mm dense open grade surface course laid to a depth of 30mm on 20mm dense open grade base binder course laided to a depth of 45mm to doe specification On 225mm well compacted cluase 804 hardcore base On Well compacted sub base to appropriate level and profile in accordance to engineers recommendations	240 m ²	
23	Drainage Supply & Install JFC 110mm dia slotted land drainage Twin-walled surface water drainage pipes. Provide 70 Linear meters of pipe to an average depth of 500mm [Backfill with clean pea gravel stone] [Or similar approved / equivalent surface water drainage pipe] Provision of 3 number soak-pits Each pit shall have 6 M3 of clean washed stone. Provide clean washed stone 75mm – 100mm Surround sides and top of soak-pits with terram geotextile T2000 (Or similar approved / equivalent geotextile)	70 Linear Meters Surface Water Drainage Pipe [Provision of 3 Number soak pits]	
24	Supply & spread high grade top soil Ground preparation, Landscape, grade, level, remove stones + seed down (Topsoil quality to be inspected and approved by Mayo County Council Parks Department prior to installation) Imported soil shall be free from Invasive Alien Plant Species (IAPS)	185m ³	

Proposed Playground at Knockmore Co Mayo

25	Landscaping Ground preparation, Landscape, grade, level, remove stones + seed down	Item	
26	Seed down with Grade 2 (Durable) Lawn seed mix	To cover 1200m ²	
27	Supply and Install Bow Top Fencing Polyester powder coated bow top fencing with self-closing gate. Heights 1.0m & 1.2m Gate width 1.0 & 1.2m for wheelchair access. See <u>Specification Sheet P</u>	130m	
28	Supply and Install Chestnut Pale Fencing 1.2m high with 75mm Gaps, 2.0mm heavily galvanised steel wire binding; Unpeeled chestnut stake support posts at 2.0m centres	45m	
29	Site De-Mobilisation Removal of all plant, equipment, materials, waste, compound, welfare facilities, construction signage, temporary fencing leaving site in a tidy and safe manner	Item	
30	Clean up and make good On completion of the works clean and tidy the site	Item	
31	Handover Provide training for maintenance of facility Provide 2 no copies maintenance schedule	Item	
32	Post Installation Report Conducted by registered playground inspector	1 Number	
33	Any item not included	Item	
34	Any item not included	Item	
Total excluding VAT			€
Total including VAT			€