

**Phase 01: Refurbishment of existing court.
The Sandy Banks, Keel, Civil & Surfacing works.**

PRICING DOCUMENT			
Item	Description	Quantity	Total
1	Insurances Health & Safety Including independent certification	Item	
2	Project Managment & Supervision of Works	Item	
3	Project supervisor construction stage	Item	
4	Provision of all tools, plant and equipment required to complete the works in a safe manner	Item	
5	Removal existing concrets posts, chain link fencing & Tennis Court net, etc.. Manually clean/ remove existing organic debris from the tarmac surface. All material to be removed to such extent as to expose the existing tarmac surface. Any material removed from the proposed site shall be taken to a licensed facility [Transport vehicle shall have all valid licences, registrations, permit and all relevant documentation]	607 Sq M	

Phase 01: Refurbishment of existing court.
The Sandy Banks, Keel, Civil & Surfacing works.

6	Site removal & ground preparation. Strip ground where relevant, grade to required formation levels. All material, soil, aggregate, waste material removed from the site shall be taken to a licensed facility. (Transport vehicle shall have all valid licences, registrations, permit and all relevant documentation)	10 M ³	
7	Supply and lay Terram Geotextile T2000 Geotextile membrane over entire pitch + Path formations areas [Or similar approved / equivalent Geotextile membrane]	607 Sq M	
8	Pitch construction Supply and lay a depth of 30mm of 4-6mm dust, level roll and compact	183 M ³	
9	Supply and lay 150 x 150 Kerbs Kerbs shall be hydraulically pressed quality concrete kerb—bedded and well haunched to true line level	106 Linear Meters	
10	Supply and install <u>Synthetic surfacing</u> <u>Refer to Specification sheet 01 A</u> Synthetic surfacing or similar approved / equivalent surfacing	607 Sq M	
11	Supply and install standard Line Marking [Five aside soccer & <u>Tennis</u>]	Item	

Phase 01: Refurbishment of existing court.
The Sandy Banks, Keel, Civil & Surfacing works.

12	Supply and install <u>Tennis Court Centre Net, Posts and fittings</u> [Assembly fixtures shall be stainless with vandal proof security elements] Posts shall be galvanised and powder coated green [ral 6005]	Item	
13	Synthetic surfacing Allow for brushing and prepare fo play on completion [Provide 25kg Silica Sand infill per Sq M] Refer to <u>Specification sheet 01 C</u>	15,175 kg Item	
14	Supply and install Muga Rules and regulations Signage Signage shall be installed in accordance with manufactures instruction and all relevant standards Refer to <u>Specification sheet 01 B</u>	2 Number	
15	Supply and install Department acknowledge signage <u>Typical signage specification is as follows:</u> Sign face is 2.5mm aluminium, with a Class Ref 2 reflective face Flat plate drilled for fixing to Galvanised steel post. Sign size 420 x 207mm (A3 size)	2 Number	
16	Landscaping Ground preparation, Landscape, grade, level, remove stones + seed down	Item	
17	Any areas disturbed during construction These areas shall be rectified, reinstated and make good to existing. All in accordance with Mayo County Councils Parks Department Requirements	Item	

Phase 01: Refurbishment of existing court.
The Sandy Banks, Keel, Civil & Surfacing works.

18	Site De-Mobilisation Removal of all plant, equipment, materials, waste, compound, welfare facilities, construction signage, temporary fencing leaving site in a tidy and safe manner	Item	
19	Clean up and make good On completion of the works clean and tidy the site	Item	
20	Post Installation Report Conducted by registered playground inspector	1 Number	
21	Handover Provide training for maintenance of facility Provide 2 no copies maintenance schedule	Item	
Total excluding VAT			€
Total including VAT			€