

P M GING Architect

Unit G
Tower Commercial Centre
Monastery Road
Clondalkin
Dublin D22 PN44
Mobile 086 261 6533
e-mail petergingarchitect@gmail.com

P M Ging Dip Arch FRIAI

ADAMSTOWN COMMUNITY COLLEGE / Science Room

Specification for Water, Drainage & Heating Services

(To be read in conjunction with Drawings)

Site Meetings to be arranged for detailed discussion with Architect re. Services before any work starts.

GENERAL DESCRIPTION :

Water to be connected from service in Store and Prep Room of Science Room on Second Floor (above).

Pipes and drainage to run in ceiling void of Ground Floor rooms below to 50 diam. waste pipes in corners.

Access to connections to be made by drilling through floor slab.

Water Pipework:

- 15mm copper pipework.

Sinks at Students' Pedestals:

- Laboratory tap, 600mm high, twin side outlet and single top outlet bib tap, brass body with anti-corrosive plastic coating to EN 13792, serrated nozzle outlets. Cold water supply.
- 250x250x250mm Laboratory sink, heavy duty fireclay or cast epoxy resin. Waste to be acid resistant.
- Polypropylene dilution recovery trap 2.3 litres, anti-siphon, emptied by unscrewing the base from trap, certified resistance to chemicals.

Drainage:

- 37mm Vulcathene chemical resistant drainage from all sinks.
- 2.3 litre dilution trap under fittings.
- Connection to 50 drains in corner ducts.

Cold Water:

- Cold water services to be taken from water services manifold.
- Distribution by 15 diam. Copper pipework well bracketed.
- Connections to fittings to have Ballofix isolation valves.

Hot Water:

- Hot water to both Belfast sinks only.
- Water heater in press in Prep Room – Ariston Lux Eco (or other approved) fitted with magnesium anode rod for protection.

Heating:

- Radiators and heating pipes in existing locations, to be taken down to allow wall insulation board and re-fitted.
- 2 new radiators 1.2x0.5 to be connected.