

ALLOW FOR THE SAFE ISOLATION, DISCONNECTION AND DECOMMISSIONING OF ALL EXISTING MECHANICAL AND ELECTRICAL SERVICES AFFECTED BY THE DEMOLITION OF THE EXISTING STUD WALLS. FOLLOWING CONSTRUCTION OF THE NEW FIRE-RATED STUD WALLS, REINSTATE, RECONNECT, TEST AND COMMISSION ALL AFFECTED SERVICES TO ENSURE FULL OPERATIONAL FUNCTIONALITY.

MECHANICAL CONTRACTOR SHALL ALLOW FOR THE WORKS ASSOCIATED WITH THE DECOMMISSIONING OF THE EXISTING HEATING SERVICES RADIATORS WITHIN THE CORRIDOR AREA.

**GENERAL NOTES:**

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL MECHANICAL, ELECTRICAL, ARCHITECTURAL AND STRUCTURAL DRAWINGS & SPECIFICATIONS.
2. THE CONTRACTOR SHALL CO-ORDINATE FULLY WITH ALL OTHER TRADES BEFORE COMMENCING WORK. THE MECHANICAL CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ALL THE NECESSARY INFORMATION TO ALLOW THE MAIN CONTRACTOR CO-ORDINATE ALL SERVICES.
3. THE MECHANICAL CONTRACTOR SHALL ALLOW FOR CO-ORDINATING THE MECHANICAL INSTALLATION WITH THE ELECTRICAL CONTRACTOR ON SITE. EXTRA COSTS INCURRED DUE TO THE CO-ORDINATION EXERCISE NOT BEING COMPLETED WILL NOT BE ACCEPTED BY THE ENGINEER.
4. DO NOT SCALE THIS DRAWING. ALL DIMENSIONS TO BE TAKEN ON SITE.
5. THE CONTRACTOR SHALL ALLOW FOR THE SUPPLY AND INSTALLATION OF ALL MECHANICAL SERVICES INDICATED ON THIS DRAWING.
6. THE CONTRACTOR SHALL BE RESPONSIBLE TO IDENTIFY SUITABLE FINAL ROUTES FOR PIPEWORK, MECHANICAL SERVICES, ETC. AS INDICATED ON THE DRAWINGS.
7. NEW MAINS RUN OF MECHANICAL PIPEWORK SHALL BE INSTALLED IN THE AREAS AS INDICATED. THIS IS INDICATIVE ONLY AND IF THE CONTRACTOR FINDS A MORE CONVENIENT ROUTE FOR THE MECHANICAL SERVICES ON SITE THEN THAT WILL BE ACCEPTABLE.
8. FINAL LOCATION OF ALL ITEMS OF PLANT/EQUIPMENT/PIPEWORK, ETC. SHALL BE AGREED ON SITE WITH THE EMPLOYERS REPRESENTATIVE AND THE CLIENT.
9. ALL SERVICES THROUGH FIRE BARRIERS SHALL BE SLEEVED EACH SIDE OF THE BARRIER. THE MAIN CONTRACTOR SHALL ALLOW FOR FIRE PROOFING THE OPES AFTER SERVICES IS INSTALLED.
10. THE CONTRACTOR SHALL ALLOW FOR ALL NECESSARY LABOUR, WIRING AND ATTENDANCES IN COMPLETING ALL THE MECHANICAL WORKS AS INDICATED ON THE DRAWINGS AND SPECIFICATIONS.
11. THE MECHANICAL CONTRACTOR SHALL ALLOW FOR ALL WORKS ASSOCIATED WITH THE DRAINING DOWN OF THE EXISTING HEATING SYSTEM AND RE-FILLING AND BALANCING OF THE EXISTING HEATING SYSTEM UPON COMPLETION OF THE WORKS.

FIRST FLOOR

GROUND FLOOR

DECOMMISSIONING EXISTING MECHANICAL SERVICES

|     |            |                              |                   |
|-----|------------|------------------------------|-------------------|
| T2  | 17.07.2026 | E.OLAYA                      | G.BENNDORF        |
| T1  | 14.08.2024 | K. DAVITT                    | G. BENNDORF       |
| REV | DATE       | PREPARED BY/PROJECT ENGINEER | QUALITY CHECK BY: |

M&amp;E CONSULTANT

**Galileo**  
ENERGY SERVICES

UNIT A6, M4 BUSINESS PARK, MAYNOOTH  
ROAD, CELBRIDGE, CO. KILDARE.  
Tel: 01-6274103  
[www.galileoenergy.ie](http://www.galileoenergy.ie)

Copyright©

Drawing Status

TENDER

Job Title

KILDANGAN NATIONAL SCHOOL,  
KILDANGAN,  
MONASTEREVIN,  
CO. KILDARE.

Drawing Title

DECOMMISSIONING EXISTING  
MECHANICAL SERVICES

Architect M'CLOUGHLIN ARCHITECTURE

Unit 4B, Elm House  
Millennium Park, Naas  
Co.Kildare, Ireland

Tel. 045 854 900

Scale:

1:100 @ A1

Drawn By:

E.O

Job No.

22-055

Drawing No.

DPM(001)

Rev.

T2