EXISTING REFLECTIVE CEILING PLAN
SCALE 1:100
TOTAL FLOOR AREA = 3176m2

TO BE READ IN CONJUNCTION WITH EXISTING FLOOR PLAN SV100 FOR ROOM DIMENSIONS

NOTE: EXISTING CEILINGS THROUGHOUT CONSIST OF SUSPENDED GRID AND TILE LAID HORIZONTAL AND SLOPED

BUILDING LEGEND

NOTE : LEGEND TO BE READ IN CONJUNCTION WITH ACCOMPANYING DRAWINGS, SCHEDULES AND SPECIFICATION DOCUMENTS.

EXISTING WALLS / STRUCTURE INDICATED THUS

- CLG Ceiling Height
- Ceiling Slope
- Round Light
- Tube Light
- Square Light
- Exit
- Access Panel
- Projector
- Camera
- Junction Box
- Smoke Detector
- Emergency Light
- Sensor
- Pipe
- Void

PROPOSED ROOF WORKS SHALL BE WHOLLY IN ACCORDANCE WITH THE WORKS REQUIREMENTS / SPECIFICATION TOGETHER WITH THE REQUIREMENTS OF DOES TGD 025 - 7 MINIMUM PERFORMANCE STANDARDS OF ROOF FINISHES.

NOTWITHSTANDING THE ABOVE, THE DESIGN AND CONSTRUCTION OF ALL ROOFS SHALL COMPLY WITH THE RELEVANT I.S., EN AND B.S. STANDARDS AND MEET THE REQUIREMENTS OF THE CURRENT BUILDING REGULATIONS PARTS A TO M AS APPLICABLE.

PROPOSED WATERPROOFING SYSTEM MUST HAVE A SINGLE SOURCE MANUFACTURER RELATES TO THE ENTIRE SYSTEM AS A SINGLE ENTITY INCLUDING THE WATERPROOFING MEMBRANES, INSULATION, ROOF LIGHTS AND THE WORKMANSHIP IN INSTALLING ALL OF THE ABOVE. THIS IS REQUIRED TO ELIMINATE SPLIT LIABILITY ON THIS PROJECT.

FLEXIBLE WATERPROOF MEMBRANES MUST HAVE A 30-YEAR MANUFACTURER DURABILITY STATEMENT ALONG WITH A MINIMUM OF A 25-YEAR MANUFACTURER INSURANCE BACKED GUARANTEE FOR MATERIALS, WORKMANSHIP AND THE ENTIRE INSTALLATION ON SITE FOR THE SPECIFIC PROJECT.

20-YEAR PRODUCT & WORKMANSHIP 'INSURANCE SUPPORTED COMPANY BACKED GUARANTEE' SHALL BEGIN ON THE DATE OF FINAL INSPECTION BY MANUFACTURER OF THE ROOFING WORKS.

MECHANICAL & ELECTRICAL SERVICES

REFER TO GALILEO ENERGY SERVICES DRAWINGS & SPECIFICATION

NOTE: DRAWINGS FOR TENDER PURPOSES ONLY ALL DIMENSIONS TO BE MEASURED ON SITE AND CONFIRMED BY CONTRACTOR BEFORE ORDER IS COMPLETE.

RIAI | Registered Architect | Architect Accredited in Conservation | PSDP Accreditation
2024 | G3 | P

A0

THIS DRAWING IS COPYRIGHT.
USE DIMENSIONS ONLY - DO NOT SCALE
CONTRACTORS MUST VERIFY DIMENSIONS ON SITE PRIOR TO STARTING WORK.

MCLA TENDER PURPOSES ONLY

Rev	Description:	Date:

Rev	Description:	Date:

MCLA
Unit 4B, Elm House, Millennium Park, Naas, Co. Kildare. W91 K032
T: +353(0)45 854900
E : info@mclarchitecture.ie

Client : BOM St. Kevin's College, Ballygall
Project : Proposed Climate Action Roof Works at St. Kevin's College, Ballygall, Dublin 11
Drawing Title : Survey of Existing Reflective Ceiling Plan

Project No. : 2607
Drawing No. : SV101
Scale : 1:100 @ A0
Date : Aug 2026
Drawn : Glen Forde