BUILDING LEGEND

NOTE : LEGEND TO BE READ IN CONJUNCTION WITH ACCOMPANYING DRAWINGS, SCHEDULES AND SPECIFICATION DOCUMENTS.

EXISTING WALLS / STRUCTURE INDICATED THUS

HORIZONTAL CEILINGS
EXISTING CEILING SHALL BE REMOVED AND DISPOSED, NEW ACOUSTIC GRID AND TILE CEILING SHALL BE INSTALLED TO ARCHITECTS SPECIFICATION

SLOPED CEILINGS
EXISTING CEILING SHALL BE REMOVED AND DISPOSED, NEW ACOUSTIC GRID AND TILE CEILING SHALL BE INSTALLED TO ARCHITECTS SPECIFICATION

EXISTING FLOOR TO CEILING HEIGHTS INDICATED THUS
PROPOSED CEILING SHALL BE INSTALLED TO EXISTING HEIGHTS. — CLG - 4.46 m

EXISTING SLOPES ON CEILINGS INDICATED THUS. PROPOSED CEILING SHALL BE INSTALLED TO EXISTING SLOPES. — 26.85°

OVERHEAD ROOFLIGHTS INDICATED THUS. EXISTING LININGSHALL BE REMOVED AND DISPOSED. NEW ROOFLIGHT LININGS SHALL BE INSTALLED. — 00 RL

LOCATION OF SENSORS IN EXISTING ROOF SPACE INDICATED THUS. REFER TO M&E PACKAGE FOR EXISTING SERVICE ALTERATIONS. — Sensor

LOCATION OF EXISTING PROJECTORS INDICATED THUS. ALL PROJECTORS SHALL BE TEMPORARY REMOVED AND REINSTATED UPON COMPLETION.

LOCATION OF SMOKE DETECTORS IN EXISTING ROOF SPACE INDICATED THUS. REFER TO M&E PACKAGE FOR EXISTING SERVICE ALTERATIONS.

LOCATION OF CAMERA'S INDICATED THUS. REFER TO M&E PACKAGE FOR EXISTING SERVICE ALTERATIONS.

LOCATION OF EMERGENCY EXIT LIGHTS INDICATED THUS. REFER TO M&E PACKAGE FOR EXISTING SERVICE ALTERATIONS. — EL Exit

TO BE READ IN CONJUNCTION WITH M&E PACKAGE FOR EXISTING SERVICE ALTERATIONS.

MECHANICAL & ELECTRICAL SERVICES

REFER TO GALILEO ENERGY SERVICES DRAWINGS & SPECIFICATION

NOTE: DRAWINGS FOR TENDER PURPOSES ONLY ALL DIMENSIONS TO BE MEASURED ON SITE AND CONFIRMED BY CONTRACTOR BEFORE ORDER IS COMPLETE.

PROPOSED ROOF WORKS SHALL BE WHOLLY IN ACCORDANCE WITH THE WORKS REQUIREMENTS - SPECIFICATION TOGETHER WITH THE REQUIREMENTS OF DOES TGD 021 - 7 MINIMUM PERFORMANCE STANDARDS OF ROOF FINISHES.

NOTWITHSTANDING THE ABOVE, THE DESIGN AND CONSTRUCTION OF ALL ROOFS SHALL COMPLY WITH THE RELEVANT I.S., EN AND B.S. STANDARDS AND MEET THE REQUIREMENTS OF THE CURRENT BUILDING REGULATIONS PARTS A TO M AS APPLICABLE.

PROPOSED WATERPROOFING SYSTEM MUST HAVE A SINGLE SOURCE MANUFACTURER RELATES TO THE ENTIRE SYSTEM AS A SINGLE ENTITY INCLUDING THE WATERPROOFING MEMBRANES, INSULATION, ROOF LIGHTS AND THE WORKMANSHIP IN INSTALLING ALL OF THE ABOVE. THIS IS REQUIRED TO ELIMINATE SPLIT LIABILITY ON THIS PROJECT.

FLEXIBLE WATERPROOF MEMBRANES MUST HAVE A 30-YEAR MANUFACTURER DURABILITY STATEMENT, ALONG WITH A MINIMUM OF A 20-YEAR MANUFACTURER INSURANCE BACKED GUARANTEE FOR MATERIALS, WORKMANSHIP AND THE ENTIRE INSTALLATION ON SITE FOR THE SPECIFIC PROJECT.

20-YEAR PRODUCT & WORKMANSHIP 'INSURANCE SUPPORTED COMPANY BACKED GUARANTEE' SHALL BEGIN ON THE DATE OF FINAL INSPECTION BY MANUFACTURER OF THE ROOFING WORKS.

PROPOSED REFLECTIVE CEILING PLAN
SCALE 1:100
TOTAL FLOOR AREA = 3176m2

NOTE: ALL PROPOSED CEILING UPGRADES SHALL BE CARRIED TO MATCH EXISTING CEILING HEIGHT AND SLOPES, TO BE READ IN CONJUNCTION WITH EXISTING SECTIONS - SV100

TO BE READ IN CONJUNCTION WITH EXISTING FLOOR PLAN SV100 FOR ROOM DIMENSIONS

RIAI	Registered Architect	Architect Accredited in Conservation	PSDP Accreditation
	2024	G3	P

A0

THIS DRAWING IS COPYRIGHT.
USE DIMENSIONS ONLY - DO NOT SCALE
CONTRACTORS MUST VERIFY DIMENSIONS
ON SITE PRIOR TO STARTING WORK.

MCLA

TENDER PURPOSES ONLY

Rev	Description:	Date:

Rev	Description:	Date:

MCLA

Unit 4B, Elm House,
Millennium Park,
Naas, Co. Kildare.
W91 K032
T: +353(0)45 854900
E : info@mclarchitecture.ie

Client : BOM St. Kevin's College, Ballygall

Project : Proposed Climate Action Roof Works at St. Kevin's College, Ballygall, Dublin 11

Drawing Title : Proposed Reflective Ceiling Plan

Project No. : 2607

Drawing No. : T102

Scale : 1:100 @ A0

Date : Aug 2026

Drawn : Glen Forde