D.Fallon Consulting Engineers				Client:		Q of A Primary School			Status:		Tender	
				Location:		Site Structures			Sheet No.:		1	
				Prepared:		DBE			Revision:		F02	
				Checked:		DF			Last Revised:		-	
				Date:		20.08.26			Dwg:		DG0060 & DG0061	

Member	Bar Mark	Type and Size	No. of mbrs	No. of bars in each	Total No.	Length of each bar ⇳ (mm)	Shape Code	A * (mm)	B * (mm)	C * (mm)	D * (mm)	E/R * (mm)
Section Type A	01	H12	1	266	266	1625	11	300	1350	~	-	-
	02	H12	1	133	133	1600	21	750	150	750	~	~
Section Type B	03	H12	1	240	240	1525	11	300	1250	~	~	~
	02	H12	1	120	120	1600	21	750	150	750	~	~

12No. Sheets of A393 Mesh with fly ends (Includes 15% for laps) (Retaining Walls)

5No. Sheets of A252 Mesh with fly ends (Includes 15% for laps) (RC Plinth)

* Specified in multiples of 5mm ⇳ Specified in multiples of 25mm

Status: P: Preliminary T: Tender C: Construction