

River Dodder Barrier Mitigation Project - Topographic and Bathymetric Survey NBMP_0895001

Response to Tender Queries No.2

Issued: 17th September 2026

No.2.1

In the BOQ it doesn't have a line item to put in the 14 additional cross sections you required survey in section 3.2?

(In addition to the cross sections described prior, cross sections are to be recorded 10m upstream of the upstream edge of each weir and bridge, for a total of 14no cross sections (6no weirs and 8no bridges).)

Also do you require all the sections related to the weirs and bridges surveyed to the OPW specification as you don't state any of this in the specification? If this is the case there would be a lot more sections required to be surveyed

Response

An updated pricing schedule has been uploaded which includes a line for the additional sections (Item no.20).

Additional cross sections have now been included at a distance downstream of the weirs and bridges. Other pertinent items from the OPW specification applicable to this project are covered in the details related to both weirs in sections 3.5.1 and bridges in sections 3.5.2. In this last section related to bridges a requirement has been added for an additional cross section of the bridge should the bridge change section along its length.

The specification has been revised up to Issue 4. The changes are highlighted in yellow from the previous issue and they are in sections 3.2 and 3.5.2.

Note:

The following tender documents have been amended, and tenders shall use the most recently issued documents to complete and submit where appropriate with their tender.

- Topographic and Bathymetry Survey Specification
- Pricing Schedule