Client:	Health Service Executive (HSE)	Project:	Proposed Boundary Retaining Wall at St Josephs Hospital	REF;	1900-BB-01
				DRG. No	1900-T01-001
Address:	St Josephs Hospital, Stranorlar, Co. Donegal	Title:	RC Wall	PAGE	1
				DATE	20/08/2025
				INITIAL	C.P.
				REVIS.	I.P.
				CHECKED	

DSM Consulting Engineers
Donegal Road, Ballybofey,
Co. Donegal.
Tel: +353 (74) 9175603
E-mail: info@dsmengineers.ie

Member	Bar Mark	Type	Size	No. of mbrs	No. in each	Total No.	Length of each bar	Shape code	A	B	C	D	E/r
RC Wall Base													
U-Bar	1	H	10	1	284	284	1840	21	170	1500	170		
Dist. Bars	2	H	10	1	90	90	6000	00	6000				
L-Bars	3	H	10	1	284	284	1500	11	900	600			
RC Wall													
Horizontal Bars	4	H	10	1	80	80	6000	00	6000				
Vertical Bars	5	H	10	1	224	224	1800	00	1800				
U-Bars	6	H	10	1	112	112	970	21	400	170	400		

Note: Contractor to check and verify all dimensions & totals before bending.
Any discrepancies to be brought to the attention of Engineer