


****FOR REMEDIATION****






EXTENT OF PLASTERBOARD CEILINGS IN
LOCALIZED ZONES TO BE REMOVED FOR
INSPECTION AND REMEDIATION OF THE
FOLLOWING:

- SLAB PENETRATIONS
- JUNCTION AT TOP OF FIRE RATED WALLS AND UNDERSIDE OF FIRST FLOOR SLAB, SECOND FLOOR SLAB & ROOF
- SERVICES PENETRATIONS THROUGH FIRE RATED WALLS.

SCOPE FOR PLASTERBOARD CEILING
REMOVAL SUBJECT TO INCREASE
DEPENDING ON EXTENT OF STEEL BEAMS
DISCOVERED REQUIRING ENCASEMENT.


ASSUMED PLUMBING WASTE SLAB
PENETRATION WITHIN CEILING VOID



Copyright in all documents and drawings prepared by AFEC Engineering Ltd, and in any works executed from those documents and drawings shall remain the property of AFEC Engineering Ltd, unless otherwise agreed at project inception

This drawing is to be read in conjunction with all relevant engineers & specialist drawings, specifications and contract documents. Work to figured dimensions only. All documents to be verified by the contractor on site. All discrepancies should be reported to the architect prior to commencement of the works.

P02	22.06.2026	Issued for Tender		RB	DM	CG
P01	12.06.2026	Issued for Tender		RB	DM	CG
REV	DATE	DESCRIPTION		DRWN BY	CHKD BY	APPD BY



1. EXTERNAL WALL CONSTRUCTION
 - 1.1 INNER LEAF: 215MM BLOCK ON FLAT
 - 1.2 OUTER LEAF: RENDER/100MM BLOCK ON EDGE
2. INTERNAL WALLS CONSTRUCTION
 - 2.1 PARTY WALLS: 215MM BLOCK ON FLAT
 - 2.2 APARTMENT INTERNAL PARTITIONS: 100MM BLOCK ON EDGE
 - 2.3 RISERS:
 - REAR WALL - 100MM BLOCK ON EDGE
 - FRONT WALL - STUD PARTITIONS WITH PLASTERBOARD LINING

AFEC JOB NO.
24304

SCALE (@ A1)
1:100

STATUS

REVISION
P02