

Electrical Builders Work Schedule

For

Electrical Tender

At

Teagasc
Oak Park
Carlow

Schedule of Builders Works

Item	Description	Cost €
1	<u>External Services / Site Works:</u> a) Provide trenching and 150mm dia wavin pipes c/w long radius bends and ¼" pull rope for pulling EV Power cables through. Include for excavating, sanding 0.15m below and above pipe, marker tape, back-filling, compacting and making good. Rocks to be removed from back-fill. b) Manholes and inspection chambers associated with above c) Provide trenching for SUB Main cabling from existing MDB to the new SDB1. Include for excavating, sanding 0.15m below and above pipe, marker tape, back-filling, compacting, disposal of surplus soil and making good. Rocks to be removed from back-fill.	€ € €
2	<u>Mechanical & Electrical Plant:</u> a) Builder to provide 2000L x 600W x 150H concrete plinth, external Sub-Distribution Board	€
3	<u>Openings in External & Internal Walls:</u> Provide the following openings in external and internal walls and allow for making good afterwards. Please refer also to the builders works drawing for wall opes requirements. a) Electrical Services Installation • 5 No. 300mm x 300mm opes • 10 No. 100mm diameter opes	€ €
8	<u>Fire Stopping:</u> Electrical Services Installation: • 5 No. 300x300mm wall opes. • 10 No. 100mm diamterwall opes.	€

		€
	Total (carry forward to Q.S. Main Bill of Quantities)	€