

PROPOSED LOCATION OF LPG TANK AND ROUTE FOR GAS MAIN
12-10-26
REV 2

 Cavan County Museum

EXISTING 40FT GREEN
CONTAINER TO BE
TEMPORARILY REMOVED AND
RE-INSTATED ONCE GAS LINE
HAS BEEN INSTALLED.

NEW 63mm PE GAS MAIN TO
BE SUPPLIED & INSTALLED BY
MECHANICAL CONTRACTOR.

GAS MAIN TO BE LAID A
MINIMUM OF 600mm BELOW
FINISHED GROUND LEVEL IN
A TRENCH C/W 200 X 200
SAND SURROUND ALL BY
MECHANICAL CONTRACTOR.

NEW 1 TONNE LPG TANK TO
BE INSTALLED IN THIS
LOCATION

SUITABLY SIZED CONCRETE
BASE AND FENCING C/W 2 X
GATES TO BE INSTALLED BY
MECHANICAL CONTRACTOR

63mm PE PIPEWORK
CHANGES TO 50mm STEEL AT
THIS LOCATION AND RUNS,
SURFACE MOUNTED AROUND
WALL BEFORE ENTERING
BUILDING

NOTE: FINAL ROUTE OF GAS
MAIN TO BE CONFIRMED ON
SITE DURING MANDATORY
SITE VISIT

Virginia Rd

Virginia Rd