



- NOTES:
1. DO NOT SCALE. USE FIGURED DIMENSIONS ONLY FROM ARCHITECTS' DRAWINGS.
  2. MECHANICAL SUB-CONTRACTOR WILL COORDINATE THE FINAL POSITIONS OF ALL EQUIPMENT AND SERVICES WITH ALL OTHER TRADES. COST INCURRED DUE TO LACK OF COORDINATION WILL NOT BE ENTERTAINED.
  3. ALL DIMENSIONS TO BE CHECKED ON SITE PRIOR TO FABRICATION.
  4. ALL PIPEWORK SHALL BE MILD STEEL
  5. PIPE WORK SUPPORTS ARE OMITTED FOR CLARITY.
  6. AIR VENTS TO BE PROVIDED AT ALL HIGH POINTS IN THE SYSTEM AND DRAIN COCKS TO BE PROVIDED AT ALL LOW POINTS IN THE SYSTEM
  7. FINAL LOCATION OF WALL MOUNTED TEMPERATURE STATS TO BE AGREED ON SITE.
  8. TRV'S TO BE INSTALLED ON ALL RADIATORS
  9. ALL CONCEALED PIPEWORK TO BE THERMALLY INSULATED



## TENDER

**rmce**  
Mechanical & Electrical Engineering

RONAN MEALLY CONSULTING ENGINEERS LTD  
City Wall, James Street  
Kilkenny  
reland  
R95 XF97  
Telephone: 056 7795428  
Email: info@rmce.ie

2 Ardliath  
Rosstownlagh  
Co Donegal  
F94 FC89  
Telephone: 087 7460260  
Email: info@rmce.ie

B332-21-0001  
BALTINGLASS GARDA STATION  
CO WICKLOW

# MECHANICAL SERVICES PROPOSED LAYOUT

|     |          |                   |        |
|-----|----------|-------------------|--------|
| N   | SCALE    | JOB NO. 22K217    |        |
| RM  | 1:100    | DRAWING No. M-100 | REV T1 |
| KED | DATE     |                   |        |
| RM  | OCT 2024 |                   |        |