Note:

MAIN CONTRACTOR SHALL BE RESPONSIBLE FOR TRAFFIC MANAGEMENT WHEN UNDERTAKING WORKS IN ZONE 3. WORKS TO BE UNDERTAKEN OUT OF HOURS BETWEEN 5PM AND 11PM. MAIN CONTRACTOR SHALL CIRCULATE TRAFFIC MANAGEMENT PLAN TWO WEEKS PRIOR TO WORKS COMMENCING FOR UHK'S APPROVAL.

AREA TO BE PLANED TO FACILITATE LONGITUDINAL AND TRANSVERSE JOINTS HATCH THUS (TYP)

ALL TRANSVERSE JOINTS (13.7M) TO BE IN ACCORDANCE WITH STANDARD DETAIL RCD/700/3

EXISTING ROAD GULLY TO BE RETAINED AND PROTECTED

ALL LONGITUDINAL JOINTS (119M) TO BE IN ACCORDANCE WITH STANDARD DETAIL RCD/700/4

EXISTING ROAD GULLYS TO BE RETAINED AND PROTECTED

EXISTING ROAD GULLY TO BE RETAINED AND PROTECTED

NEW 2M X 2M X 0.8M DEEP SOAKAWAY COMPRISING 95% VOID RATIO MODULAR CELLULAR CRATES

NEW 150MM STORM WATER PIPELINE CONNECTING ACO DRAIN/SILT TRAP TO SOAKAWAY

NEW SILT TRAP

AREA (330M²) SHOWN THUS TO BE EXCAVATED TO A DEPTH OF 200MM TO REMOVE EXISTING PAVEMENT CONSTRUCTION AND REGULATED WITH 100MM CLAUSE 804 GRANULAR MATERIAL COMPACTED IN ACCORDANCE WITH SPECIFICATION. NEW PAVEMENT TO CONSIST OF 40MM THICK SMA 14 PMB SURF 65/105-60 DES WEARING COURSE ON 60MM THICK AC 20 DENSE BIN 70/100 DES BINDER COURSE

ALL ROAD MARKINGS TO BE REINSTATED AS PER ORIGINAL LAYOUT (TYP)

NEW HIGH CAPACITY ACO DRAIN (29M) (SEE DETAIL ON DRG. NO. 12626-116) TO BE DISCHARGE TO NEW SOAK AWAY

ROAD SURFACE TO BE REINSTATED TO ORIGINAL LEVELS, ORIGINAL LEVELS DENOTED THUS (TYP)

ALL ROAD MARKINGS TO BE REINSTATED AS PER ORIGINAL LAYOUT (TYP)

ALL ROAD MARKINGS TO BE REINSTATED AS PER ORIGINAL LAYOUT (TYP)

PEDESTRIAN CROSSING ROAD MARKINGS TO BE REINSTATED

HOSPITAL MAIN ENTRANCE

EXISTING ROAD GULLY TO BE RETAINED AND PROTECTED

PEDESTRIAN CROSSING ROAD MARKINGS TO BE REINSTATED

GRASS

STONE

MKPOST

ESB LP

TIMBER COVER

MHR 7.14 IC 7.15 NO.COVER

MHR 7.00

MHS 6.88

ICE 6.87

MH237 CL 6.83 IL 5.68

MH240 CL 6.86 IL 6.33

MH244 CL 6.98 IL 5.62

PARAPET 11.03

PARAPET 11.02

BENCH

BICYCLE STANDS

SIGN

FL 7.07

Notes:

1. ALL DIMENSIONS ARE IN MILLIMETRES – FIGURED DIMENSIONS TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS.
2. ALL LEVELS ARE IN METERS AND RELATE TO ORDINANCE DATUM MARLIN HEAD.
3. MAIN CONTRACTOR TO CONFIRM ALL DIMENSIONS & LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORKS. ALL DISCREPANCIES TO BE REPORTED TO DESIGN OFFICE.

Legend:

1. WORKS ZONE OUTLINE SHOWN THUS IN RED .....
2. LONGITUDINAL JOINT DENOTED THUS ..... LJ
3. TRANSVERSE JOINT DENOTED THUS ..... TJ

Issue	Date	Revisions	Drawn	Checked	Approved
0	09.10.26	Issued for Tender	NO'M	MW	MW

UNIVERSITY HOSPITAL KERRY
OSPIDÉAL NA hOLLSCOILE, CIARRAÍ
A UNIVERSITY AFFILIATED ACUTE HOSPITAL

MRG consulting engineers
No.4 Day Place, Tralee, County Kerry.
T :(066)7123130 Fax :(066)7123364 E-Mail :info@mrg.ie
also: Elysium Business Centre, Second Floor, Breffni House, Watercourse Road, Blackpool, Cork.
MRG Consulting Engineers Limited Civil Structural Architectural Environmental

Project
University Hospital Kerry
Internal & External Upgrade Works

Drawing
Zone 3 – Entrance/Set Down Area
Road Upgrade Works

Drawn	N.O'Mahony	Project No.	Drawing No.
Date	25.08.2026	126026	126026-113
Scale	1:100 @ A1		