WORKS REQUIREMENTS

Steel Palisade Fencing Installation

Tipperary County Council

Project Location: Ard Gaoithe Clonmel

Project Particulars

Employer: Tipperary County Council

PSCS: Successful Contractor

Preliminary Safety and Health Plan: To be issued to successful Contractor

Setting Out and Tolerances: Contractor Responsibility

GPR Survey: Contractor Responsibility

Site Security: Contractor Responsibility

Works Requirements

1. Scope of Works

- Site establishment and mobilisation.
- Setting out of all works.
- GPR Survey and utility detection.
- Excavation and installation of fence posts and foundations.
- Supply and installation of steel palisade fencing and gates.
- Provision and maintenance of site security.
- Protection of existing services.
- Reinstatement of disturbed surfaces.
- Health and safety documentation.
- As-built records and completion documentation.

2. Project Supervisor Construction Stage (PSCS)

- Contractor shall act as PSCS and fulfil all statutory duties.
- Prepare and maintain Construction Stage Safety and Health Plan.
- Coordinate contractors and manage risks.
- Compile Safety File information.

3. GPR Survey and Service Detection

- Undertake GPR survey before excavation.
- Identify and mark services.
- Provide survey report prior to excavation.

4. Site Security

- Contractor responsible for site security throughout the contract.
- Provide barriers, signage and protection measures.

5. Setting Out and Tolerances

- Contractor wholly responsible for all setting out.
- Verify dimensions, levels, boundaries and alignments.
- Achieve all horizontal and vertical tolerances.
- Correct errors at own expense.

6. Existing Services

- Locate, protect and maintain existing services.

7. Access and Working Areas

- Responsible for access routes and working areas.
- Make good any damage caused.

8. Environmental Management

- Control pollution, dust, noise and waste.

9. Completion Documentation

- Provide as-built drawings, warranties, records and Safety File information.

10. Contractor General Responsibilities

- All costs deemed included in Contract Sum including PSCS duties, GPR, site security, setting out and ancillary works.