17

Legend:

Existing Roof I.D No, 01 Roof Finishes To Be Upgraded.= 373.0msq
Existing Roof I.D No, 02 Roof Finishes To Be Upgraded.= 51.60msq
Existing Roof I.D No, 03 Roof Finishes To Be Upgraded.= 109.0msq
Existing Roof I.D No, 04 Roof Finishes To Be Upgraded.= 101.0msq
Existing Roof I.D No, 05 Roof Finishes To Be Upgraded.= 73.15msq
Existing Roof I.D No, 06 Roof Finishes To Be Upgraded.= 52.15msq
Existing Roof I.D No, 07 Roof Finishes To Be Upgraded.= 95.78msq

TOTAL ROOF AREA TO BE UPGRADED = 855.68msq.

NOTES

N W E S

CHURCHFIELD TERRACE W

ROOF I.D No. '04' (Roof Area = 101.0msq)
ROOF I.D No. '03' (Roof Area = 109.0msq)
ROOF I.D No.'05' (Roof Area = 73.15msq)
ROOF I.D No.'06' (Roof Area = 52.15msq)
ROOF I.D No.'07' (Roof Area = 95.78msq)
ROOF I.D No. '02' (Roof Area = 51.6msq)
ROOF I.D No. '01' (Roof Area = 373.0msq)

See Detail 'B' (Drg 26001-03)
See Detail 'C' (Drg 26001-03)
See Detail 'C' (Drg 26001-03)
See Detail 'C' (Drg 26001-03)
See Detail 'D' (Drg 26001-03)
See Detail 'A' (Drg 26001-03)
See Detail 'E' (Drg 26001-03)
See Detail 'F' (Drg 26001-03)
See Detail 'A' (Drg 26001-03)
See Detail 'G' (Drg 26001-03)
See Detail 'A' (Drg 26001-03)

WATER TOWER.
PRE-FAB-01
Existing Pre-Fab-02
OLD SCHOOL BUILDING
OLD SCHOOL BUILDING
STORE
Existing School.
Existing Chimney
Existing High Point.
Existing Stairs
Existing Lift
Step
Existing High Point.
20153
19664
Fall.

'A' 'B' 'C' 'D' 'E' 'F'

Proposed New Roof Finish Specification.
New Roof Membrane Of IKO Ultra Prevent 25 Torch On Cap Sheet, On A IKO Ultra Heat Underlay Sheet, On 120mm IKO Supertherm ALU Insulation Board, (Note: To Achieve A Fall Of 1:60 Use Taper Insulation Where Required.) On Pro Sprayfast IBA Adhesive Primer, On A IKO ULTRA Self-Adhesive Vapour Control Layer (VCL). On A IKO Pro ULTRA Bonding Agent, All Laid On The Existing Roof Finishes That Should Be Washed And Dryed, Including Dust Free Prio To Any Roof Finishes Application.

EXISTING ROOF LAYOUT PLAN .
Scale: 1:125

Rev.	Description	By	Date
C	For Tender	EM	30.10.26
B	Stage 2B Approval	EM	10.08.26
A	For Tender	EM	13/03/26

The copyright of this drawing is vested in the Engineers and it must not be copied or reproduced without their written concent. Figured dimensions only should be taken from this drawing. All Contractors must visit the site and must be responsible for taking and checking all dimensions that relate to this work.

PMCG CONSULTING ENGINEERS
77 Main Street
Macroom, Co. Cork
026 24123
pat@pmcgcork.ie

Client: SCOIL PADRE PIO-(Churchfield)

Project: UPGRADE OF EXISTING ROOFS.

Drawing: MASTER PLAN OF EXISTING ROOF LAYOUT TO BE UPGRADED.

Scale	Drawn By	Checked By
1:125 @ A1	EM	PC

Job No.	Drawing No.	Issue
26001	01	C