Legend:

Through Line Of Edge Detail 'A' . Circa Of 79.0m In Length (See Drawing 26001-03-Rev-C)

Through Line Of Edge Detail 'B' . Circa Of 132.6m In Length (See Drawing 26001-03-Rev-B)

Location Of Existing Rain PVC Water Roof Outlets To Be Upgraded Total Of 16No. R.W.O

Location Of Existing PVC Soil Vent Pipes Outlets To Be Upgraded Total Of 02No. S.V.P

17

CHURCHFIELD TERRACE W

ROOF I.D No. '03' (Roof Area = 109.0msq)

ROOF I.D No. '04' (Roof Area = 101.0msq)

ROOF I.D No.'05' (Roof Area = 73.15msq)

ROOF I.D No.'06' (Roof Area = 52.15msq)

ROOF I.D No.'07' (Roof Area = 95.78msq)

ROOF I.D No. '02' (Roof Area = 51.6msq)

ROOF I.D No. '01' (Roof Area = 373.0msq)

WATER TOWER.

PRE-FAB-01

OLD SCHOOL BUILDING

STORE

Existing Chimney

Existing High Point.

Existing Stairs

Existing Lift

Step

Existing Pre-Fab-02

Existing School.

See Verge Detail 'B' (Drg 26001-03)

See Verge Detail 'A' (Drg 26001-03)

R.W.O 01, R.W.O 02, R.W.O 03, R.W.O 04, R.W.O 05, R.W.O 06, R.W.O 07, R.W.O 08, R.W.O 09, R.W.O 10, R.W.O 11, R.W.O 12, R.W.O 13, R.W.O 14, R.W.O 15, R.W.O 16, R.W.O 17

S.V.P 01, S.V.P 02

Fall.

'A' 'B' 'C' 'D' 'E'

Proposed New Roof Finish Specification.
New Roof Membrane Of IKO Ultra Prevent 25 Torch On Cap Sheet, On A IKO Ultra Heat Underlay Sheet, On 120mm IKO Supertherm ALU Insulation Board, (Note: To Achieve A Fall Of 1:60 Use Taper Insulation Where Required.) On Pro Sprayfast IBA Adhesive Primer, On A IKO ULTRA Self-Adhesive Vapour Control Layer (VCL). On A IKO Pro ULTRA Bonding Agent, All Laid On The Existing Roof Finishes That Should Be Washed And Dryed, Including Dust Free Prio To Any Roof Finishes Application.

NOTES

N W E S

EXISTING ROOF LAYOUT PLAN (I.D No. 01).

Scale: 1:125

Rev.	Description	By	Date
B	For Tender	EM	30.10.26
A	Stage 2B Approval	EM	10/08/26

The copyright of this drawing is vested in the Engineers and it must not be copied or reproduced without their written concent. Figured dimensions only should be taken from this drawing. All Contractors must visit the site and must be responsible for taking and checking all dimensions that relate to this work.

PMCG CONSULTING ENGINEERS
77 Main Street
Macroom, Co. Cork
026 24123
pat@pmcgcork.ie

Client: SCOIL PADRE PIO-(Churchfield)

Project: UPGRADE OF EXISTING ROOFS.

Drawing: EXISTING ROOFS SHOWING AREAS & RAINWATER OUT LETS & VENTS.

Scale	Drawn By	Checked By
1:125 @ A1	EM	PC

Job No.	Drawing No.	Issue
26001	08	B