	(10) PREPARED SITE				
	DEMOLITION AND ALTERATIONS				
	DEMOLITION				
	General clearance				
A	remove sod and stone fence to road level; dispose off site	m	17.10		

COLLECTION

Page No. 1/1

(10) PREPARED SITE
Carried to Summary

Date of Printing: 13/08/2026 05:32

	(30) SITE ENCLOSURES				
	SURFACE PAVINGS, FENCING AND LANDSCAPING				
	FENCING				
	Fencing				
A	1400mm high timber post and wire fence to Architects specification	m	20		
	Extra over for				
B	end posts	nr	4		
C	angle posts	nr	2		
D	straining posts	nr	2		
	Gates				
E	Galvanized steel double leaf gate; total width 5850mm and height 1500mm; with padlock and bolt frame. Ground anchor to one leaf	nr	1		
	Gate posts				
F	250x250 timber gate posts; 1800mm high	nr	2		
	GRASSING AND PLANTING				
	Hedges				
G	Hedging to Architect's specification	m	17.10		
	Maintenance for Defects Liability Period				
H	Maintain hedge for the defects liability period.	item	1		
J					

COLLECTION

Page No. 2/1

(30) SITE ENCLOSURES
Carried to Summary

SUMMARY	**Page No.**
(10) PREPARED SITE	1/2
(30) SITE ENCLOSURES	2/2

TOTAL AMOUNT TO FORM OF TENDER

Note: This Bill of Quantities contains pages numbered 1/1 to 2/2.