

New FD 60s fire doors including frames, seals and ironmongery to replace existing (D5, 6 & 7)

New FD 30s fire doors including frames, seals and ironmongery to replace existing. (D1, 2 & 9)

FD 30s Fire doors including frames, seals and ironmongery + REI 30 partition*. 850mm clear width. 5nr on ground floor. (D3, 4, 8, 10 & 11)

*30 min enclosure of stairs - Partition: Gyproc Gypwall 102mm partition thickness with 1 x 5mm Gyproc fireline board, max height of 3800mm heavy duty rating with 70mm Gypframe 'C' studs at 600mm C/C.

NOTE: - Door sizes

Unless a specific door measurement is indicated on the drawing adjacent to the door concerned, or indicated on the legend, all door openings and associated dimensions are to be assessed and verified on site by the Contractor prior to manufacture or installation.

The Contractor is responsible for taking all necessary site measurements and ensuring that the proposed door sizes are suitable for the existing openings and site conditions. Any discrepancies or issues identified on site are to be brought to the attention of the ER prior to proceeding.

Revisions

Date:	Description:	Drawn by:
September '26	Initial draft for review	ND

Project: Proposed fire safety upgrades to Pearse Officer's Mess

Location: Pearse Officer's Mess - DFTC East

Drawing: New doors - Ground floor

Drawing Number:	Scale:
DFTC - 28 - 26A - 1002	1:100 A1
Surveyed By:	Drawn By: Niall Darby
Date: October '26	Checked By: Comdt Shane Phelan