




Door 12




Door 13




Doors 14 & 15




Door 16



Door 17




Door 18



Door 19



Door 20




Door 21




Door 22



Doors 23 & 24



Door 25



Door 26

First floor doors:

Door 12: Door to bedroom No. 16. Existing frame to door is damaged and is to be removed carefully back to original brickwork. Door to also be removed and replaced with new as per door schedule.

Door 13: New door and partition to be installed in the area as shown on photo and drawing. New partition to also be installed. Ceiling height of ~3.46m. Width of corridor ~1.21m.

Doors 14 & 15: New doors and partition to be installed as shown. Partition to extend to underside of FF ceiling. Ceiling height of ~3.45m and width of corrideor ~1.79m

Door 16: Entrance to stairwell 6. Door and frame to be carefully removed and replaced with new as per schedule.

Door 17: Entrance to sauna / shower room. Door and frame to be carefully removed and replaced with new as per schedule.

Door 18: Entrance to laundry room. Door and frame to be carefully removed and replaced with new as per schedule.

Door 19: Electrical switch room. Door and frame to be carefully removed and replaced with new as per schedule. (FD 60s).

Door 20. New door and partition to be installed in area as shown. Ceiling height ~2.99m and width of corridor ~ 1.13m

Door 21: Door and frame to be carefully removed and replaced with new as per schedule.

Door 22: New door and partition to be installed in this area as shown on drawing. Ceiling height of ~3.46m and width of corridor ~1.79m.

Doors 23 & 24: New doors and partition to be installed as shown on drawing. Ceiling height of ~3.51m and width of corridor ~1.79m.

Door 25: New door and partition to be installed in this area. Ceiling height of ~3.47m and width of corridor ~1.2m.

Door 26: Door to bedroom 17. Door and frame to be carefully removed and replaced with new as per schedule.

NOTE: All doors, frames etc to be measured and dimensions confirmed on site by contractor. **All new doors in partitions to have - Fire door keep shut - signs on either side of door.**

Revisions

Date:	Description:	Drawn by:
September '26	Initial draft for review	ND

Project: Proposed fire safety upgrades to Pearse Officer's Mess

Location: Pearse Officers Mess - DFTC East

Drawing: Existing first floor doors to be refurbished / installed

Drawing Number:	Scale:
DFTC - 28 - 26A - 1012	NTS
Surveyed By:	Drawn By: Niall Darby
Date: October '26	Checked By: Comdt Shane Phelan