PRICING DOCUMENT

(Name of Firm) .....
For the following Works:- Culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.

The item descriptions listed hereunder are necessarily brief and are provided to assist the Tenderer in the preparation of his estimate. Tenderers shall include in their estimate for all other works (whether of a permanent or temporary nature) associated with these items which are explicitly or reasonably to be inferred from the Specification, Drawings, or other contract documents. Any other items considered necessary, or requiring separate pricing, should be listed by Tenderers after the items listed below.

Item No.	Item Description	No.	Unit	Rate €	Cost €
1	**GENERAL**				
1.1	Mobilisation/Demobilisation.	1	Item		
1.2	Insurances.	1	Item		
1.3	Health & Safety requirements	1	Item		
1.4	Project Supervisor Construction Stage.	1	Item		
1.5	Site Security	1	Item		
1.6	Water Diversion Requirements & Security	1	Item		
1.7	Traffic Management	1	Item		
2	**EXCAVATION REQUIREMENTS**				
2.1	Excavate out existing gardens and footpaths, and playground, as outlined in Section 2.1 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	345	M^3		
3	**PLAYGROUND RAILING TEMPORARY REMOVAL**				
3.1	Carefully remove and store existing playground railing panels, as outlined in Section 2.2 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	70	M		
3.2	Carefully remove and store existing playground railing uprights, as outlined in Section 2.2 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	24	No.		
3.2	Carefully remove and store existing playground furniture, and bins, as outlined in Section 2.2 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	14	No.		
	PAGE SUB TOTAL	-	-	-	

Item No.	Item Description	No.	Unit	Rate €	Cost €
Carried forward from previous page		-	-	-	
4	**DRAINAGE**				
4.1	Supply and lay new precast drainage culverts, to falls as required, to tie in with existing culvert, as outlined in Section 2.3.1 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	75	M		
4.2	Supply and install new collar joint detail, as outlined in Section 2.3.2 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	1	No.		
4.3	Supply and lay new access chamber in precast culvert, as outlined in Section 2.3.3 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	1	No.		
4.4	Line existing egg shaped brick culvert, as outlined in Section 2.3.4 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	100	M		
5	**LANDSCAPING**				
5.1	Landscaping and top soiling, as per Section 2.4 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	280	M^2		
6	**FOOTPATH CONSTRUCTION**				
6.1	Construction of new footpath, as per Section 2.5 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	200	M^2		
6.2	Construction of European larch board path edging to new footpath, as per Section 2.5 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	100	M		
7	**EDGE KERBING CONSTRUCTION**				
7.1	Install new concrete edge kerbs, as outlined in Section 2.6 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park, to match existing.	70	M		
	PAGE SUB TOTAL	-	-	-	

Item No.	Item Description	No.	Unit	Rate €	Cost €
Carried forward from previous page		-	-	-	
8	**PLAYGROUND REINSTATEMENT**				
8.1	Carefully reinstate stored playground railing uprights, as outlined in Section 2.7.1 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	24	No.		
8.2	Carefully reinstall playground railing panels, as outlined in Section 2.7.2 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	70	M		
8.3	Carefully reinstate stored playground furniture, and bins, as outlined in Section 2.7.3 of 3251-TD-007 culvert repairs and ancillary works, Peoples Gardens, Phoenix Park.	14	No.		
	TENDER TOTAL	-	-	-	