© Martin Peters Associates

A1




Tailte Éireann Licence No. CYAL50364565
© National Mapping Division of Tailte Éireann

EX MH

EX MH

EX MH

EX MH

150mm Ø WASTEWATER

EX MH

APPROX LOCATION OF EXISTING 300mm Ø STORMWATER SEWER TO BE RETAINED UNALTERED

300mm Ø STORMWATER

EX MH

S1.0
CL: +32.44
IL: +30.99

PROPOSED RG TO TAKE OUTFALL FROM FUTURE CANOPIES TO DISCHARGE TO PROPOSED STORMWATER SEWER

PROPOSED STORMWATER SEWER

Ex. RG

EXISTING ROAD GULLIES TO BE REMOVED AND REPLACED WITH EXISTING CONNECTION TO MAIN SEWER RETAINED

450mm Ø COMBINED

EXMH
CL:
IL:

EX MH

EXMH

Ex. RG

EXISTING ROAD GULLIES TO BE REMOVED AND REPLACED WITH EXISTING CONNECTION TO MAIN SEWER RETAINED

225mm Ø WASTEWATER

450mm Ø COMBINED

Ex. RG

EX MH

Ex. RG

EXISTING ROAD GULLIES TO BE REMOVED AND REPLACED WITH EXISTING CONNECTION TO MAIN SEWER RETAINED

450mm Ø COMBINED

17

15

13

11

## EXISTING DRAINAGE

CONTRACTOR TO ALLOW FOR JETTING & CLEANING OF THE FULL EXTENT OF STORMWATER SEWER (750M), ALL EXISTING GULLY CONNECTIONS TO STORM, & COMBINED SEWERS AND;
CCTV SURVEY & MAIN SEWER SEWERS THROUGH THE SITE INCLUDING WASTEWATER, COMBINED SEWER, AND STORMWATER SEWERS

# PROPOSED STORM & WASTEWATER LAYOUT SHEET 2

SCALE 1:250 @ A1 & 1:500 @ A3

## Issue Register

| No. | Date | Description | Drawn | Checked | Approved |
|---|---|---|---|---|---|
| 00 | 20/10/2026 | P8 - TENDER ISSUE | NT | EJQ | EJQ |

## GENERAL NOTES:-

1. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS & ENGINEERS DRAWINGS & SPECIFICATIONS.
2. DO NOT SCALE. USE FIGURED DIMENSIONS ONLY.
3. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS & ELEVATIONS WITH ARCHITECTURAL DRAWINGS PRIOR TO START OF CONSTRUCTION. ALL DISCREPANCIES TO BE NOTIFIED, IN WRITING TO ENGINEERS & ARCHITECTS FOR RESOLUTION.
4. ALL DIMENSIONS ON DRAWINGS ARE IN MILLIMETRES UNLESS OTHERWISE NOTED.
5. FOR DETAILS AND SETTING OUT OF RWP, SVP, WVP & ALL OPENINGS SEE THE RELEVANT ARCHITECTS DRAWINGS.
6. FOR RADON BARRIER, D.P.C. & INSULATION DETAILS REFER TO ARCHITECTS DRAWINGS.

ALL SETTING OUT DIMENSIONS TO BE CHECKED AGAINST ARCHITECTS DRAWINGS. ARCHITECTS DRAWINGS TO TAKE PRECEDENCE.

## GENERAL LEGEND:-

- DENOTES SITE BOUNDARY
- DENOTES LAND OWNERSHIP BOUNDARY
- DENOTES EXISTING BUILDING
- DENOTES OUTLINE OF FUTURE SOLAR CANOPY
- 0.000m — DENOTES EXISTING GROUND LEVEL
- FFL +0.000m — DENOTES PROPOSED FOUNDATION TOC LEVEL

## STORM LEGEND:-

- EX MH — DENOTES EXISTING STORM SEWER & MANHOLE COVER AND FRAME TO BE REMOVED AND REPLACED TO NEW COVER LEVEL
- Ex. RG — DENOTES EXISTING ROAD GULLY TO BE REMOVED AND REPLACED TO NEW COVER LEVEL WITH EXISTING BRANCH PIPE TO BE RETAINED
- S1.0 CL: IL: — 350mm @1:60 — DENOTES PROPOSED STORM SEWER & MANHOLE
- RG — DENOTES PROPOSED ROAD GULLY & 150mmØ BRANCH PIPE CONNECTION @ 1:80
- EX — DENOTES EXISTING COMBINED SEWER & MANHOLE COVER AND FRAME TO BE REMOVED AND REPLACED TO NEW COVER LEVEL
- EX MH — DENOTES EXISTING WASTEWATER SEWER & MANHOLE COVER AND FRAME TO BE REMOVED AND REPLACED TO NEW COVER LEVEL

Client:
WATERFORD & WEXFORD EDUCATION AND TRAINING BOARD

Project:
PROPOSED CARPARK UPGRADES & ALTERATIONS
WATERFORD TRAINING CENTRE

Drawing Title:
PROPOSED STORM & WASTEWATER LAYOUT SHEET 2

| Project | Originator | Phase | Element | Spatial Zone | Level | Type | Role | Number |
|---|---|---|---|---|---|---|---|---|
| 261049 | MPA | X | X | X | XXX | DR | CE | 1301 |

| Drawn | Checked | Date | Scale | Purpose | Revision |
|---|---|---|---|---|---|
| RB | EJQ | 04/11/26 | 1:250 | P8 - TENDER | 00 |

Martin Peters Associates
Consulting Engineers
Ormonde Road, Kilkenny, R95 AHX8 | T: +353 56 7702761 | E: info@mpa.ie | W: www.mpa.ie
ISO 9001 QUALITY MANAGEMENT